CONTRACT NO. 83964

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 3509 | 00-00173-00-FP | COOK | 246 | 8 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 7 | ILLINOIS | FED. AID PROJECT | | |

SUMMARY OF QUANTITIES

| CODE NO | PAY ITEM | UNIT | QUANTITY | I000-2A ROADWAY WILMETTE 70% STU 30% STATE | I000-2A ROADWAY EVANSTON 70% STU 30% STATE | Y030-1E LIGHTING WILMETTE 70% STU 30% LA | Y030-1E LIGHTING EVANSTON 70% STU 30% LA | Y031-1F SIGNALS WESTERFIELD 70% STU 30% LA | Y031-1F SIGNALS LAKE 70% STU 30% LA | Y031-1F SIGNALS ISABELLA 70% STU 30% LA | Y003-TEA ENHANCEMENTS WILMETTE 80% ITEP 20% LA | Y060 WATER WILMETTE NON-PART 100% LA | Y060 WATER EVANSTON NON-PART 100% LA |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 78300100 | * PAVEMENT MARKING REMOVAL | SQ FT | 9,082 | 741 | 8,341 | | | | | | | | |
| 81000600 | * CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 751 | | | | | 159 | 26 | 566 | | | |
| 81000700 | * CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 1,768 | | | 1,064 | 480 | 142 | 30 | 52 | | | |
| 81000800 | * CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 33 | | | | | 0 | 21 | 12 | | | |
| 81001000 | * CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL | FOOT | 246 | | | | | 4 | 52 | 10 | | 180 | |
| 81018500 | * CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 1,279 | | | | | 371 | 741 | 167 | | | |
| 81018600 | * CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 372 | | | 120 | | 252 | 0 | 0 | | | |
| 81018900 | * CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 627 | | | | | 133 | 226 | 268 | | | |
| 81400100 | * HANDHOLE | EACH | 16 | | | | | 5 | 6 | 5 | | | |
| 81400200 | * HEAVY-DUTY HANDHOLE | EACH | 5 | | | | | 2 | 2 | 1 | | | |
| 81400300 | * DOUBLE HANDHOLE | EACH | 4 | | | | | 1 | 1 | 2 | | | |
| 81400735 | * HANDHOLE, COMPOSITE CONCRETE, SPECIAL | EACH | 131 | | | 90 | 11 | | | | 30 | | |
| 81603155 | * UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1" DIA. POLYETHYLENE | FOOT | 23,005 | | | 14,014 | 4,320 | | | | 4,671 | | |
| 81800230 | * AERIAL CABLE, 2-1/C NO. 6 WITH MESSENGER WIRE | FOOT | 15,275 | | | 11,525 | 3,750 | | | | | | |
| 81900200 | * TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 22,052 | | | 17,175 | 3,860 | 273 | 104 | 640 | | | |
| 83057140 | * LIGHT POLE, WOOD, 30 FOOT, CLASS 3 | EACH | 75 | | | 66 | 9 | | | | | | |
| 83600200 | * LIGHT POLE FOUNDATION, 24" DIAMETER | FOOT | 16 | | | | 16 | | | | | | |
| 83600400 | * POLE FOUNDATION, METAL | EACH | 27 | | | 27 | | | | | | | |
| 84200600 | * REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE | EACH | 11 | | | 11 | | | | | | | |
| 84200700 | * LIGHTING FOUNDATION REMOVAL | EACH | 15 | | | 13 | 2 | | | | | | |
| 84400105 | * RELOCATE EXISTING LIGHTING UNIT | EACH | 15 | | | 13 | 2 | | | | | | |
| 85700200 | * FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 2 | | | | | 1 | 1 | | | | |
| 85700205 | * FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL | EACH | 1 | | | | | | | 1 | | | |
| 87301215 | * ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 1,882 | | | | | 453 | 601 | 828 | | | |
| 87301225 | * ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 3,699 | | | | | 840 | 1,739 | 1,120 | | | |
| 87301245 | * ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 3,134 | | | | | 1,358 | 573 | 1,203 | | | |
| 87301255 | * ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 2,684 | | | | | | 1,858 | 826 | | | |
| 87301305 | * ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR | FOOT | 3,432 | | | | | 954 | 1,385 | 1,093 | | | |
| 87301805 | * ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C | FOOT | 519 | | | | | 125 | 213 | 181 | | | |
| 87701140 | * STEEL MAST ARM ASSEMBLY AND POLE, 20 FT. (SPECIAL) | EACH | 1 | | | | | | | 1 | | | |
| 87701150 | * STEEL MAST ARM ASSEMBLY AND POLE, 22 FT. (SPECIAL) | EACH | 1 | | | | | | | 1 | | | |
| 87701170 | * STEEL MAST ARM ASSEMBLY AND POLE, 26 FT. (SPECIAL) | EACH | 2 | | | | | | | 1 | 1 | | |
| 87701200 | * STEEL MAST ARM ASSEMBLY AND POLE, 32 FT. (SPECIAL) | EACH | 2 | | | | | | | 1 | 1 | | |
| 87701220 | * STEEL MAST ARM ASSEMBLY AND POLE, 36 FT. (SPECIAL) | EACH | 1 | | | | | | | | 1 | | |
| 87701230 | * STEEL MAST ARM ASSEMBLY AND POLE, 38 FT. (SPECIAL) | EACH | 1 | | | | | | | | 1 | | |
| 87704040 | * STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT. (SPECIAL) | EACH | 1 | | | | | | | | 1 | | |
| 87704050 | * STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT. (SPECIAL) | EACH | 1 | | | | | | | | 1 | | |
| 87800100 | * CONCRETE FOUNDATION, TYPE A | FOOT | 40 | | | | | 24 | 8 | 8 | | | |
| 87800150 | * CONCRETE FOUNDATION, TYPE C | FOOT | 12 | | | | | 4 | 4 | 4 | | | |
| 87800400 | * CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER | FOOT | 90 | | | | | 30 | 15 | 45 | | | |

* SPECIALTY ITEM

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHERIDAN ROAD

DATE 7/13/07
DRAWN BY LTD
CHECKED BY BJL

PLOT DATE = 7/12/2007
FILE NAME = g:\cad85\0095\rroad\sheets\SUMQTY.sht
PLOT SCALE = 50.0000 ' / IN.
USER NAME = b.johnson

TranSystems
1051 PERIMETER DRIVE, SUITE 1025
SCHAUMBURG, ILLINOIS 60173
(847) 605-9600