

SUMMARY OF QUANTITIES

FAS ROUTE NO	SEC	COUNTY	TOTAL SHEETS	SHEET NO
-	*	DEKALB	21	2
ILLINOIS PROJECT BRS-1122(107)				
* 04-00206-00-BR				

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	FEDERAL FUNDING CODE X-020-2A (STRUCTURE)	FEDERAL FUNDING CODE X-1000 (ROADWAY)	NON-PARTICIPATING 100% LOCAL COUNTY FUNDING CODE X-1000
20200100	EARTH EXCAVATION	CU YD	3540	0	460	3080
20400800	FURNISHED EXCAVATION	CU YD	950	0	124	827
20800150	TRENCH BACKFILL	CU YD	25	0	0	25
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.49	0	0	1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800	0	104	696
28000300	TEMPORARY DITCH CHECKS	EACH	25	0	3	22
28000400	PERIMETER EROSION BARRIER	FOOT	400	0	52	348
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	964	0	125	839
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	26	0	0	26
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.76	0	5.12	5
40600982	HOT-MIX ASPHALT SURFACE COURSE REMOVAL - BUTT JOINT	SQ YD	532	0	0	532
40603080	HOT MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	3151	0	1500	1651
40603305	HOT MIX ASPHALT SURFACE SOURCE, MIX "C", N30	TON	1119	0	740	379
48101200	AGGREGATE SHOULDERS, TYPE B	TON	188	0	75	113
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	0	0
50300225	CONCRETE STRUCTURES	CU YD	25.1	25	0	0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	153.5	154	0	0
50300260	BRIDGE DECK GROOVING	SQ YD	222	222	0	0
50300300	PROTECTIVE COAT	SQ YD	242	242	0	0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6595	6595	0	0
50700305	HARDWARE	POUND	3084	3084	0	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20,320	20320	0	0
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	87	87	0	0
51201005	FURNISHING METAL SHELL PILES 12"	FOOT	583	583	0	0
51203200	TEST PILE METAL SHELLS	EACH	1	1	0	0
51500100	NAME PLATES	EACH	1	1	0	0
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	84	0	0	84
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	250	0	250	0
542A0241	PIPE CULVERTS, CLASS A, TYPE 1, 36"	FOOT	115	0	0	115
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	940	0	940	0
△ 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	550	0	550	0
△ 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4	0	4	0
△ * 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	0	3	0
△ * 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	0	1	0
* 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	414	0	414	0
△ 78001100	PAINT PAVEMENT MARKINGS - LETTERS AND SYMBOLS	SQ FT	54.2	0	10	44
△ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4268	0	555	3713
△ 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	754	0	0	754
△ 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	43	0	0	43
△ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	78	0	0	78
△ * 78200455	BIDIRECTIONAL GUARD RAIL REFLECTORS	EACH	12	0	12	0
△ * 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	0	4	0
* X5121800	PERMANENT STEEL SHEET PILING	SQ FT	3550	3550	0	0
51202305	DRIVING PILES*	FOOT	583	583		
* 67100100	Mobilization	LSum	1	1		

△ SPECIALTY ITEMS

Revised 8-27-07 1

* revised 8-28-07

QUANTITY NOTES:

*SEE SPECIAL PROVISIONS
 PERIMETER EROSION BARRIER IS AN ESTIMATED QUANTITY. LOCATIONS ARE TO BE DESIGNATED IN THE FIELD BY THE ENGINEER.

SUMMARY OF QUANTITIES
 SECTION 04-00206-00-BR
 CHERRY VALLEY ROAD
 DEKALB COUNTY