

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	1000 ROADWAY	1007 STRUCTURE
20200100	EARTH EXCAVATION	CU YD	962	962	
Δ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	51	51	
Δ 28000300	TEMPORARY DITCH CHECKS	EACH	7	7	
Δ 28000500	INLET AND PIPE PROTECTION	EACH	4	4	
Δ 28100108	DUMPED RIPRAP, SPECIAL	TON	129		129
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4'	SQ YD	842	842	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12'	SQ YD	1335	1335	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	543	543	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6878	6878	
40600300	AGGREGATE (PRIME COAT)	TON	150	150	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	257	257	
40600990	TEMPORARY RAMP	SQ YD	84	84	
Δ 40603100	HOT-MIX ASPHALT BINDER COURSE, IL-19.0L, N30	TON	12393	12393	
Δ 40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N30	TON	7484	7484	
Δ 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	69	69	
Δ 42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7'	SQ YD	794	794	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5391	5391	
Δ 48300200	PORTLAND CEMENT CONCRETE SHOULDERS 7'	SQ YD	127	127	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
51500100	NAME PLATES	EACH	1		1
Δ 54103900	CORRUGATED STRUCTURAL PLATE PIPE ARCHES 46 SQ. FT.	FOOT	82	82	
Δ 54200271	PIPE CULVERTS, CLASS C, TYPE 1 66'	FOOT	5	5	
Δ 54205923	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 48'	FOOT	7	7	
Δ 54205929	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 54'	FOOT	12	12	
Δ 54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18'	FOOT	36	36	
Δ 54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18'	EACH	2	2	
54215163	STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 48'	EACH	2	2	
Δ 67100100	MOBILIZATION	L SUM	1	1	
Δ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
Δ 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3095	3095	
○ 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123	
○ 78001140	PAINT PAVEMENT MARKING - LINE 8'	FOOT	102	102	
○ 78001150	PAINT PAVEMENT MARKING - LINE 12'	FOOT	122	122	
○ 78001180	PAINT PAVEMENT MARKING - LINE 24'	FOOT	93	93	
Δ X0320547	REMOVE AND REINSTALL END SECTION	EACH	6	6	
Δ X0976500	END SECTIONS TO BE REMOVED	EACH	2	2	
Δ X5121800	PERMANENT STEEL SHEET PILING	SQ FT	216		216
Δ XX003565	SEEDING SPECIAL, COMPLETE	ACRE	0.51	0.51	
Δ XX003643	BASE REPAIR, SPECIAL	SQ YD	1500	1500	
Δ Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
* Δ Z0076600	TRAINEES	HOUR	1000	1000	
Δ XX006942	PIPE CULVERTS, CLASS D, TYPE 2 EQUIVALENT ROUND-SIZE 120'	FOOT	116		116
Δ XX006943	REMOVAL OF CORRUGATED STRUCTURAL PLATE PIPE ARCH BEVELED END SECTION	FOOT	62	62	
Δ	SEE SPECIAL PROVISIONS				
○	SPECIALTY ITEM				
*	Y080				

DRAWN BY: L.A.G.
 CHECKED BY: D.J.D.

CAD/.DWG: SUMQUANS
 DATE: 04/07

REVISIONS	
DATE	BY

CHAMLIN ASSOCIATES
 PERU MORRIS ILLINOIS

C.H. 33 (ANGLING ROAD)
 2007
 SECTION 05-00198-00-RS

SUMMARY OF QUANTITIES

Drawing Name: C:\Users\LV813\Documents\Projects\05-00198-00-RS\05-00198-00-RS.dwg
 Date: 04/07/07
 Time: 2:45:00 PM
 User: LV813