

# SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	00-00164-00-SP	TAZEWELL	80	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				STU 70% FEDERAL 30% LOCAL 1000-1A	100% LOCAL 1000-1A	HHS 90% FEDERAL 10% LOCAL SFTY-1A	HHS 90% FEDERAL 10% LOCAL Y030-1E	HHS 90% FEDERAL 10% LOCAL Y031-1F	HHS 90% FEDERAL 10% LOCAL SFTY-1D
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	111	111					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	28	28					
20200100	EARTH EXCAVATION	CU YD	2135	2068	67				
20800150	TRENCH BACKFILL	CU YD	172	172					
21101615	TOPSOIL, FURNISH AND PLACE 4"	SO YD	1617	1617					
25200110	SODDING, SALT TOLERANT	SO YD	1576	1576					
28000400	PERIMETER EROSION BARRIER	FOOT	519	519					
28000500	INLET AND PIPE PROTECTION	EACH	5			5			
31100300	SUBBASE GRANULAR MATERIAL, TYPE A, 4"	SO YD	3962	3962					
35101400	AGGREGATE BASE COURSE, TYPE B	TON	591	552	39				
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SO YD	2082	2082					
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SO YD	580	580					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1359	1359					
40600300	AGGREGATE (PRIME COAT)	TON	27	27					
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	660	660					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	244	244					
40600990	TEMPORARY RAMP	SO YD	163	163					
40603560	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	1185	1185					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	98	53	45				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	1097	1097					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	9004	9004					
42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SO FT	995	995					
42400800	DETECTABLE WARNINGS	SO FT	34			34			
44000100	PAVEMENT REMOVAL	SO YD	61	61					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	5027	5027					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	2160	2160					
44000300	CURB REMOVAL	FOOT	569	569					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3445	3445					
44000600	SIDEWALK REMOVAL	SO FT	7141	7141					
44003100	MEDIAN REMOVAL	SO FT	49	49					
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SO YD	4			4			
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	107			107			
50104400	CONCRETE HEADWALL REMOVAL	EACH	2			2			
50800105	REINFORCEMENT BARS	POUND	140			140			
542A0223	PIPE CULVERTS, CLASS A, TYPE 1, 18"	FOOT	54			54			
54213663	PRECAST REINFORCED CONCRETE END SECTIONS 18"	EACH	2			2			
54248500	CONCRETE HEADWALLS	CU YD	0.7			0.7			
54248510	CONCRETE COLLAR	CU YD	2.0			2.0			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	176			176			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	14			14			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	3			3			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	49			49			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	33			33			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	388			388			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2			
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2			2			
60241800	INLETS, TYPE G-1	EACH	8			8			
60255500	MANHOLES TO BE ADJUSTED	EACH	3			3			
60262800	INLETS TO BE RECONSTRUCTED (SPECIAL)	EACH	1			1			
60500060	REMOVING INLETS	EACH	1			1			
60500065	REMOVING INLETS, SPECIAL	EACH	1			1			
60600605	CONCRETE CURB, TYPE B	FOOT	99.5	99.5					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	341.5	341.5					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3435.5	3435.5					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION STANDARD 701606	L SUM	1			1			
70102632	TRAFFIC CONTROL AND PROTECTION STANDARD 701602	L SUM	1			1			
70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L SUM	1			1			
70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L SUM	1			1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	944						944
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SO FT	164						164
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7235						7235
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	873						873
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	529						529
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	228						228
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4144			4144			

\* DESIGNATES SPECIALTY ITEM

