

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	00-00164-00-SP	TAZEWELL	80	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**42400100 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH**

LOCATION	SO FT	REMARKS
26+80.00 TO 32+00.00 LT	2428.6	
32+00.00 TO 36+99.46 LT	2068.0	
34+50.00 TO 34+92.30 RT	736.8	
37+75.96 TO 42+00.00 LT	1658.5	
87+28.00 TO 89+00.00 LT	739.8	
88+31.30 TO 89+00.00 RT	413.6	
91+00.00 TO 92+59.82 LT	958.9	
TOTAL: 9004		

**42400420 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL**

LOCATION	SO FT	REMARKS
35+63.80 TO 37+50.00	323.1	
37+50.00 TO 38+49.65	671.8	
TOTAL: 995		

**42400800 DETECTABLE WARNINGS**

LOCATION	SO FT	REMARKS
33+01.33 TO 33+06.10	10.0	
34+17.55 TO 34+21.98	9.0	
34+19.16 TO 34+23.73	9.0	
87+32.28 TO 87+34.54	6.0	
TOTAL: 34		

**44000100 PAVEMENT REMOVAL**

LOCATION	SO YD	REMARKS
31+16.53 TO 32+00.00	17.9	
32+00.00 TO 32+86.80	43.5	
TOTAL: 61		

**44000198 HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)**

LOCATION	SO YD	REMARKS
26+90.00 TO 32+00.00	1631.1	
33+00.00 TO 37+50.00	1256.1	
37+50.00 TO 40+04.00	239.8	
86+78.38 TO 89+25.00	901.0	
90+75.00 TO 92+90.00	998.6	
TOTAL: 5027		

**44000200 DRIVEWAY PAVEMENT REMOVAL**

LOCATION	SO YD	REMARKS
27+21.20 TO 27+77.52 LT	23.3	FIELD ENTRANCE
30+40.90 TO 30+88.76 LT	77.5	COMMERCIAL ENTRANCE
31+04.04 TO 31+49.86 LT	76.7	COMMERCIAL ENTRANCE
31+62.08 TO 32+21.87 LT	102.6	COMMERCIAL ENTRANCE
32+54.89 TO 33+07.65 LT	77.1	COMMERCIAL ENTRANCE
35+06.88 TO 35+73.95 LT	32.9	PARKING LOT
35+76.22 TO 35+97.64 LT	53.1	COMMERCIAL ENTRANCE
36+37.32 TO 36+59.48 LT	34.1	COMMERCIAL ENTRANCE
36+59.48 TO 37+00.00 RT	18.4	PARKING LOT
37+00.00 TO 37+50.00 RT	61.7	COMMERCIAL ENTRANCE
34+86.47 TO 35+00.00 RT	34.2	COMMERCIAL ENTRANCE
35+00.00 TO 35+50.63 RT	245.5	COMMERCIAL ENTRANCE
35+51.80 TO 36+95.49 RT	203.6	PARKING LOT
36+93.45 TO 37+37.51 RT	88.1	COMMERCIAL ENTRANCE
37+31.73 TO 37+50.00 RT	9.3	PARKING LOT
37+50.00 TO 38+00.00 LT	71.1	PARKING LOT
38+00.00 TO 38+50.00 LT	64.4	COMMERCIAL ENTRANCE
38+50.00 TO 39+00.00 LT	83.7	COMMERCIAL ENTRANCE
39+00.00 TO 39+50.00 LT	77.3	PARKING LOT
39+50.00 TO 39+98.49 LT	94.7	COMMERCIAL ENTRANCE
41+13.93 TO 41+42.31 LT	21.8	COMMERCIAL ENTRANCE
37+50.00 TO 38+00.00 LT	13.3	PARKING LOT
38+00.00 TO 38+50.00 RT	6.6	PARKING LOT
38+50.00 TO 38+94.65 RT	134.7	COMMERCIAL ENTRANCE
86+68.36 TO 87+00.00 RT	33.3	PARKING LOT
87+00.00 TO 87+50.00 RT	79.8	PARKING LOT
87+50.00 TO 87+69.79 RT	36.5	COMMERCIAL ENTRANCE
87+69.79 TO 88+00.00 RT	63.1	COMMERCIAL ENTRANCE
88+00.00 TO 88+31.42 RT	65.7	COMMERCIAL ENTRANCE
88+32.19 TO 88+56.65 LT	61.5	COMMERCIAL ENTRANCE
88+67.74 TO 89+16.34 RT	94.3	COMMERCIAL ENTRANCE
91+43.21 TO 92+26.71 LT	8.8	PARKING LOT
92+55.79 TO 92+90.60 LT	11.4	COMMERCIAL ENTRANCE
TOTAL: 2160		

**44000300 CURB REMOVAL**

LOCATION	EQ FT	REMARKS
31+60.83 TO 31+77.10 LT	29.7	COMMERCIAL ENTRANCE
32+10.72 TO 32+21.90 LT	25.0	COMMERCIAL ENTRANCE
32+54.87 TO 32+64.24 LT	23.3	COMMERCIAL ENTRANCE
32+96.55 TO 33+08.73 LT	31.0	COMMERCIAL ENTRANCE
35+39.78 TO 35+50.63 RT	49.3	COMMERCIAL ENTRANCE
35+75.34 TO 35+76.24 LT	24.1	COMMERCIAL ENTRANCE
35+98.17 TO 35+98.37 LT	23.3	COMMERCIAL ENTRANCE
37+29.94 TO 37+29.52 RT	58.2	COMMERCIAL ENTRANCE
37+01.62 TO 37+01.60 RT	64.1	COMMERCIAL ENTRANCE
38+51.59 TO 38+59.69 RT	43.1	COMMERCIAL ENTRANCE
38+89.51 TO 38+89.66 RT	43.8	COMMERCIAL ENTRANCE
87+69.57 TO 87+83.81 RT	31.4	COMMERCIAL ENTRANCE
88+16.27 TO 88+31.42 RT	26.3	COMMERCIAL ENTRANCE
88+34.66 TO 88+34.92 LT	20.3	COMMERCIAL ENTRANCE
88+62.66 TO 88+71.62 RT	26.6	COMMERCIAL ENTRANCE
89+03.06 TO 89+11.41 RT	38.2	COMMERCIAL ENTRANCE
92+54.93 TO 92+60.06 LT	11.7	COMMERCIAL ENTRANCE
TOTAL: 569		

**44000500 COMBINATION CURB AND GUTTER REMOVAL**

LOCATION	EQ FT	REMARKS
26+80.00 TO 31+00.00 LT	388.2	
26+80.00 TO 31+00.00 RT	520.0	
31+60.73 TO 31+91.16 RT	65.0	MEDIAN
32+15.51 TO 33+36.00 LT	104.5	
32+00.00 TO 33+35.55 RT	156.9	
33+27.81 TO 33+39.77 RT	36.1	ISLAND
33+94.99 TO 34+04.05 LT	36.5	ISLAND
33+96.15 TO 37+50.00 RT	295.1	
34+00.00 TO 37+50.00 LT	363.2	
35+19.24 TO 35+62.66 LT	88.5	MEDIAN
37+50.00 TO 40+14.00 RT	221.4	
37+50.00 TO 40+14.00 LT	264.0	
40+90.14 TO 41+59.30 LT	69.2	
86+68.36 TO 89+25.00 RT	187.7	
86+68.36 TO 86+90.87 LT	39.8	
87+20.37 TO 89+25.00 LT	199.3	
90+75.00 TO 93+00.00 RT	225.0	
90+75.00 TO 93+00.00 LT	184.5	
TOTAL: 3445		

**44000600 SIDEWALK REMOVAL**

LOCATION	SO FT	REMARKS
26+80.00 TO 30+49.33 LT	1537.7	
30+80.17 TO 31+11.21 LT	98.7	
31+42.60 TO 31+66.86 LT	64.5	
32+10.83 TO 32+63.86 LT	183.9	
33+01.34 TO 33+36.81 LT	204.3	
34+00.47 TO 35+14.27 RT	717.4	
34+03.04 TO 35+97.38 LT	874.3	
35+39.19 TO 37+00.41 RT	667.6	
37+30.15 TO 37+50.00 RT	79.4	
37+50.00 TO 38+59.09 RT	404.7	
38+90.24 TO 39+07.08 RT	67.4	
40+36.04 TO 41+73.62 LT	590.2	
87+25.14 TO 88+32.19 LT	416.6	
88+56.27 TO 89+25.00 LT	280.2	
89+09.36 TO 89+25.00 RT	64.1	
90+75.00 TO 92+59.14 LT	890.1	
TOTAL: 7141		

**44003100 MEDIAN REMOVAL**

LOCATION	SO YD	REMARKS
31+63.32 TO 31+90.50	13.0	
33+28.35 TO 33+39.36	7.4	
33+95.49 TO 34+03.55	4.0	
35+21.15 TO 35+61.85	24.6	
TOTAL: 49		

**44200140 PAVEMENT PATCHING, TYPE I, 12 INCH**

LOCATION	SO YD	REMARKS
92+40.00 TO 92+46.00	3.9	STORM SEWER SS-1
TOTAL: 4		

**44200144 PAVEMENT PATCHING, TYPE II 12 INCH**

LOCATION	SO YD	REMARKS
33+22.75 TO 33+51.80	8.1	
33+51.80 TO 33+81.55	8.8	STORM SEWER SS-5
33+22.90 TO 33+61.00	12.2	
33+61.00 TO 33+86.70	7.5	STORM SEWER SS-7
33+86.70 TO 34+22.95	10.5	STORM SEWER SS-8
36+23.03 TO 36+47.78	9.6	
36+44.60 TO 36+64.81	9.6	STORM SEWER SS-11
38+11.12 TO 38+24.61	12.4	
38+19.25 TO 38+32.79	12.5	STORM SEWER SS-15
88+17.25 TO 88+24.50	6.4	STORM SEWER SS-9
88+21.06 TO 88+35.78	9.1	STORM SEWER SS-10
TOTAL: 107		

**50104400 CONCRETE HEADWALL REMOVAL**

LOCATION	LT	EACH	REMARKS
29+22.28		1	
29+25.64		1	
TOTAL: 2			

**50800105 REINFORCEMENT BARS**

LOCATION	LT	EQUND	REMARKS
27+79.04		30.0	18" COLLAR
27+91.63		30.0	18" COLLAR
28+19.00		20.0	D18-1 1/2 HEADWALL
28+91.67		30.0	18" COLLAR
29+52.43		30.0	18" COLLAR
TOTAL: 140			

**542A0223 PIPE CULVERTS, CLASS A, TYPE 1, 18"**

LOCATION	EX	FES-1	EQ FT	REMARKS
FES-2 TO EX			45.0	CULVERT CVT-1
FES-2 TO EX			9.0	CULVERT CVT-2
TOTAL: 54				

**54213663 PRECAST REINFORCED CONCRETE END SECTIONS 18"**

LOCATION	LT	EACH	REMARKS
28+15.42		1	STRUCTURE FES-1
27+84.18		1	STRUCTURE FES-2
TOTAL: 2			

**54248500 CONCRETE HEADWALLS**

LOCATION	LT	CU YD	REMARKS
29+19.00		0.7	TYPE D18-1 1/2
TOTAL: 0.7			

**54258510 CONCRETE COLLAR**

LOCATION	LT	CU YD	REMARKS
27+79.04		0.5	18" COLLAR
27+91.63		0.5	18" COLLAR
28+90.00		0.5	18" COLLAR
29+52.43		0.5	18" COLLAR
TOTAL: 2.0			

**550A0050 STORM SEWERS, CLASS A, TYPE 1 12"**

LOCATION	IN-6	IN-7	EQ FT	REMARKS
IN-6 TO IN-7			64.8	STORM SEWER SS-6
IN-7 TO MH-2			89.4	STORM SEWER SS-7
IN-9 TO MH-3			21.6	STORM SEWER SS-9
TOTAL: 176				

**550A0070 STORM SEWERS, CLASS A, TYPE 1 15"**

LOCATION	IN-1	MH-5	EQ FT	REMARKS
IN-1 TO MH-5			14.0	STORM SEWER SS-1
TOTAL: 14				

