

MUNICIPALITY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
QUINCY	06-00300-00-LS	ADAMS	69	6

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE	CONSTRUCTION TYPE	CONSTRUCTION TYPE
				CODE	CODE	CODE
				I000	Y030 (2)	Y031 (2)
(1)	60266600*VALVE BOXES TO BE ADJUSTED	EACH	19	19		
	60267100*METER VAULTS TO BE RECONSTRUCTED	EACH	2	2		
	60500060 REMOVING INLETS	EACH	1	1		
	60500305 FILLING INLETS	EACH	4	4		
	60600605 CONCRETE CURB, TYPE B	FOOT	1183	1183		
	60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	642	642		
	67100100 MOBILIZATION	L SUM	1	1		
	70101800*TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
(1)	70300100 SHORT-TERM PAVEMENT MARKING	FOOT	2578	2578		
(1)	70300230 TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	4371	4371		
(1)	70300240 TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3258	3258		
(1)	70300260 TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	40	40		
(1)	70300280 TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	404	404		
(1)	70301000 WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4895	4895		
	72000100 SIGN PANEL - TYPE 1	SQ FT	51	51		
(1)	78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS (2) AND SYMBOLS	SQ FT	225	225		
(1)	78000300 THERMOPLASTIC PAVEMENT MARKING - LINE 5" (2)	FOOT	6298	6298		
(1)	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6" (2)	FOOT	3258	3258		
	* SEE SPECIAL PROVISIONS					

(1) NON-PARTICIPATING ITEM FOR TRANSPORTATION ENHANCEMENT FUNDING

(2) SPECIALTY ITEMS

SUMMARY OF QUANTITIES
SHEET 3 OF 7