



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 5, 2007

SUBJECT: FAU 7622 (Jackson Avenue)
Project BRM-5013(15)
Section 06-00085-00-BR (Charleston)
Coles County
Contract No. 95522
Item 23
September 21, 2007 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Revised page 1 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric Harm
Interim Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." monogram.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

STATE OF ILLINOIS
CITY OF CHARLESTON

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction, adopted January 1, 2007, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of Section No. 06-00085-00-BR in Coles County, Illinois, and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

DESCRIPTION OF WORK

The work included in this contract consists of removal of an existing single span concrete structure, construction of a three sided precast concrete structure with pile bent footings, PCC base course, HMA surface course, segmental concrete block retaining walls, earthwork, storm sewer relocation, sidewalk and other associated work as listed in the plans.

CONSTRUCTION REQUIREMENTS:

It is the intent of the City that the new bridge be constructed and completed by June 30, 2008. Work shall be scheduled such that Jackson Avenue will remain open to traffic during the winter shut down period. See also the TRAFFIC CONTROL PLAN and the COMPLETION DATE special provision for other requirements.

TRAFFIC CONTROL PLAN

Traffic control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual of Uniform Traffic Control Devices for Streets and Highways, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 and section 701 of the Standard Specifications for Road and Bridge Construction and the following (1) Highway Standards, (2) Supplemental Specifications and Recurring Special Provisions and (3) other Special Provisions relating to traffic control.

| | | | | |
|--------------------|--------|--------|--------|--------|
| Highway Standards: | 701001 | 701006 | 701301 | 701501 |
| | 702001 | BLR 21 | | |

Revised 9-5-07