



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 18, 2007

SUBJECT: Project SBIL-IL03(9)
Section 03-00026-00-PK (Hartford)
Madison County
Contract No 97300
Item 66
September 21, 2007 Letting
Addendum (B)

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

Proposal- Revised special provision "Fence Rail" on page 7.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Eric Harm
Interim Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

minimum slope of 1%. Cleanouts shall be placed at all bends and at the connection point of the existing (building) service line and the new service line. This work shall be constructed according to the requirements of Section 31 of the "Standard Specifications for Water and Sewer Main Construction in Illinois", adopted May, 1996 and latest revisions, except that testing will not be required.

This item of work will be measured along the sanitary sewer service line, and paid for at the contract unit price per foot for SANITARY SEWER SERVICE 6".

FENCE RAIL

This item of work consists of furnishing and installing a fence rail as shown on the plans or as directed by the Engineer.

All fence elements shall be No. 1 Southern Yellow Pine as graded by the Southern Pine Inspection Bureau and shall be pressure treated according to allowable industry standards for human contact and in compliance with the Standard Specifications.

Each piece of timber shall carry a grade stamp and quality assurance stamp indicating class of timber and chemical retention.

The posts shall be installed according to the applicable requirements of Article 630.05 Posts of the Standard Specifications. All fasteners and other metal hardware shall be according to Article 1006.29(d) of the Standard Specifications.

The fence rail shall be installed closely fitted, accurately set in place and secured using fasteners and braces as shown on the plans. "Butt" joints will not be allowed. All joints shall be bevel cut at an angle of 75 degrees, or as required by the specific layout, prior to fitting and securing the timber sections.

This work will be measured in place from centerline of end post to centerline of end post in feet and paid for at the contract unit price per foot for FENCE RAIL.

CONCRETE PAVERS

This item of work shall consist of furnishing and installing concrete pavers at the locations shown in the construction plans and according to Section 02780 – Unit Pavers of these Special Provisions.

This item of work shall be measured complete, in place, and paid for at the contract unit price per square foot for CONCRETE PAVERS.