

SUMMARY OF QUANTITIES

| | | | | |
|---------------------|---------------------------|-----------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 57/64 | (41-3)HBK | JEFFERSON | 518 | 7 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT | | | |
| CONTRACT NO. 98963 | | | | |

| CODE NO. | ITEM | UNIT | URBAN TOTAL QUANTITY | 80% FED./20% STATE | | 100% | | LIGHTING 90% FEDERAL 10% STATE <i>1030-1E</i> | TRUSS SIGN PANELS 100% STATE <i>1002-1C</i> |
|-------------|---|-------|----------------------|--------------------|----------------|---------|---------------------------------|--|--|
| | | | | ROADWAY J000-2A | BRIDGE X271-2A | ROADWAY | FAI 57/64 90% FEDERAL 10% STATE | | |
| 51204650 | PILE SHOES | EACH | 24 | | 24 | | | | |
| 51500100 | NAME PLATES | EACH | 1 | | 1 | | | | |
| * 5160 3000 | DRILLED SHAFT IN SOIL | CU YD | 68.4 | | 68.4 | | | | |
| * 5160 4000 | DRILLED SHAFT IN ROCK | CU YD | 16.3 | | 16.3 | | | | |
| 54001000 | BOX CULVERT END SECTIONS | EACH | 3 | 3 | | | | | |
| 54010402 | PRECAST CONCRETE BOX CULVERT 4' X 2' | FOOT | 4 | 4 | | | | | |
| 54010603 | PRECAST CONCRETE BOX CULVERT 6' X 3' | FOOT | 53 | 53 | | | | | |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | FOOT | 12 | | | 12 | | | |
| 542A3379 | PIPE CULVERTS, CLASS A, TYPE 5 24" | FOOT | 156 | | | 156 | | | |
| 542A5491 | PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | FOOT | 43 | | | 43 | | | |
| 54201291 | PIPE CULVERTS, TYPE 2 RCCP 36" | FOOT | 115 | 115 | | | | | |
| 54201303 | PIPE CULVERTS, TYPE 2 RCCP 48" | FOOT | 253 | 253 | | | | | |
| 54202143 | PIPE CULVERTS, TYPE 3 RCCP 48" | FOOT | 166 | 166 | | | | | |
| 54204219 | PIPE CULVERTS, TYPE 6 RCCP 24" | FOOT | 227 | 227 | | | | | |
| 54204231 | PIPE CULVERTS, TYPE 6 RCCP 36" | FOOT | 480 | 480 | | | | | |
| 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH | 8 | 8 | | | | | |
| 54213663 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" | EACH | 1 | 1 | | | | | |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | EACH | 11 | 8 | | 3 | | | |
| 54213675 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" | EACH | 2 | 2 | | | | | |
| 54213681 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36" | EACH | 6 | 6 | | | | | |
| 54213693 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48" | EACH | 6 | 6 | | | | | |
| 54214731 | PRECAST REINFORCED CONCRETE FLARED END SECTION - ELLIPTICAL EQUIVALENT ROUND-SIZE 36" | EACH | 2 | | | 2 | | | |
| 54215547 | METAL END SECTIONS 12" | EACH | 25 | 25 | | | | | |
| 54244405 | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 | EACH | 1 | 1 | | | | | |
| 54248510 | CONCRETE COLLAR | CU YD | 20.24 | 19.8 | | 0.44 | | | |
| 542JA024 | PIPE CULVERTS, CLASS A 24" (JACKED) | FOOT | 230 | 230 | | | | | |
| 5421C012 | PIPE CULVERTS, CLASS C, TYPE 1, 12" (TEMPORARY) | FOOT | 140 | 140 | | | | | |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 853 | 853 | | | | | |
| 550A0070 | STORM SEWERS, CLASS A, TYPE 1 15" | FOOT | 69 | 69 | | | | | |
| 550A0090 | STORM SEWERS, CLASS A, TYPE 1 18" | FOOT | 424 | 424 | | | | | |
| 550A0120 | STORM SEWERS, CLASS A, TYPE 1 24" | FOOT | 378 | 378 | | | | | |
| 550A0140 | STORM SEWERS, CLASS A, TYPE 1 30" | FOOT | 134 | 134 | | | | | |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 261 | 261 | | | | | |

* SPECIALTY ITEMS

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/27/2007 08:35 AM
 A:\B\106198\20196\Road\Sheet\Sheet C-601500.dgn
 LAYOUT: RLT 02/26/04
 DRAWN: JED 04/12/04
 REVIEWED: MTM 01/22/07

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

 VETERANS MEMORIAL DRIVE
 INTERCHANGE
 SECTION (41-3)HBK

 SCALE: DATE 3-22-07
 DRAWN BY RLT
 CHECKED BY MTM