

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 98963				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FED./20% STATE		1000		LIGHTING 90% FEDERAL 10% STATE Y030-1E	TRUSS SIGN PANELS 100% STATE Y002-1C
				ROADWAY J000-2A	BRIDGE X271-2A	ROADWAY FAI 57/64 90% FEDERAL 10% STATE			
55100700	STORM SEWER REMOVAL 15"	FOOT	39	39					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	187		187				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	59			59			
60100945	PIPE DRAINS 12"	FOOT	1616	1616					
60107600	PIPE UNDERDRAINS 4"	FOOT	27380			27380			
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	821			821			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	311		311				
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	3	3					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	8	8					
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1					
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	7	7					
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1					
60500040	REMOVING MANHOLES	EACH	3	3					
60500060	REMOVING INLETS	EACH	22	21		1			
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	852	852					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2534	2534					
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1169	1169					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	11070	10289		781			
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	94			94			
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	153			153			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	25215	24965		250			
60619121	CONCRETE MEDIAN, TYPE SB-6	SQ FT	11502	11502					
60900515	CONCRETE THRUST BLOCKS	EACH	50	50					
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1439	475		964			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4			4			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	6	2		4			
63500105	DELINEATORS	EACH	160			160			
64200105	SHOULDER RUMBLE STRIP	FOOT	27874			27874			
66400105	CHAIN LINK FENCE, 4'	FOOT	10065	4592		5473			
66410300	CHAIN LINK FENCE REMOVAL	FOOT	5543			5543			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
  
**VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK**

SCALE: DATE 3-22-07  
 DRAWN BY RLT  
 CHECKED BY MTM

Copyright Hanson Professional Services Inc. 2007  
**HANSON**  
 Hanson Professional Services Inc.

LAYOUT: RLT 02/26/04  
 DRAWN: JED 04/22/04  
 REVIEWED: MTM 03/22/07  
 03/27/2007, 10:35 AM  
 A:\98\98963\2007\Road\Sheets\601500.dgn