

SUMMARY OF QUANTITIES

F.A.I. RTE. 57/64	SECTION (41-3)HBK	COUNTY JEFFERSON	TOTAL SHEETS 518	SHEET NO. 10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FED. / 20% STATE		100%		LIGHTING 90% FEDERAL 10% STATE Y030-1E	TRUSS SIGN PANELS 100% STATE Y002-1C
				ROADWAY J000-2A	BRIDGE X271-2A	ROADWAY FAI 57/64 90% FEDERAL 10% STATE			
78200405	GUARDRAIL MARKERS	EACH	18			18			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	2		4			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	19385			19385			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	419			419			
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1		
81021550	CONDUIT, AUGERED, 2" DIA., PVC	FOOT	710				710		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10915				10915		
81603035	UNIT DUCT, 600V, 2-1/C NO. 6, GROUND, (XLP-TYPE USE) 1" DIA. POLYETHYLENE	FOOT	12035				12035		
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 400 WATT	EACH	41				41		
82500540	LIGHTING CONTROLLER TYPE CB-RCS 100 AMP - 480 VOLT	EACH	1				1		
83010600	LIGHT POLE, ALUMINUM, 50 FT. M.H. 15 FT. MAST ARM	EACH	41				41		
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	287				287		
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	41				41		
X0325804	MODIFIED SOIL 18"	SQ YD	8713			8713			
25000305	SEEDING, CLASS 3A	ACRE	2.75	2.75					
X0325770	TRAFFIC CONTROL AND PROTECTION (SPECIAL) CASE I	L SUM	1			1			
X0325771	TRAFFIC CONTROL AND PROTECTION (SPECIAL) CASE II	L SUM	1			1			
X0325773	TRAFFIC CONTROL AND PROTECTION (SPECIAL) CASE III	L SUM	1	0.8		0.2			
X0322729	MATERIAL TRANSFER DEVICE	TON	12,624			12,624			
X07201000	SEALING ABANDONED WATER WELLS	EACH	4			4			
X0488100	REMOVING EXISTING SEPTIC TANK	EACH	4			4			
X0022800	FENCE REMOVAL	FOOT	1,500			1,500			
X0325805	BITUMINOUS SIDEWALK REMOVAL	SQ FT	8,000			8,000			

*SPECIALTY ITEMS

Rev. 5-31-07

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 VETERANS MEMORIAL DRIVE
 INTERCHANGE
 SECTION (41-3)HBK
 SCALE: DATE 3-22-07
 DRAWN BY RLK
 CHECKED BY MTM

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.
 03/27/2007 10:36 AM
 A:\88\088\988\20\96\Road\Sheet\Sheet C-60\500.dgn
 LAYOUT: RLK 02/26/04
 DRAWN: FEO 04/12/04
 REVIEWED: MTM 03/22/07