

STONE DUMPED RIPRAP SCHEDULE - GRADE SEPARATION			
LOCATION	CLASS A3 SQ YD	CLASS A4 SQ YD	FILTER FABRIC SQ YD
VETERANS MEMORIAL DRIVE			
STA. 34+59 LT	15.4		15.4
STA. 34+57 RT	15.4		15.4
STA. 36+13 RT TO STA. 36+76 RT		211.8	211.8
STA. 36+28 LT TO STA. 36+69 LT		69.8	69.8
STA. 37+90 LT	8.0		8.0
STA. 37+90 RT	8.0		8.0
STA. 40+40 LT	8.0		8.0
STA. 40+40 RT	8.0		8.0
STA. 42+90 LT	6.2		6.2
STA. 42+90 RT	6.2		6.2
STA. 43+42 RT	16.7		16.7
STA. 43+42 LT	14.0		14.0
STA. 44+90 LT	6.2		6.2
STA. 44+90 RT	6.2		6.2
STA. 45+65 RT TO STA. 46+25 RT		84.0	84.0
STA. 45+65 LT TO STA. 46+25 LT		84.0	84.0
STA. 47+40 LT	6.2		6.2
STA. 47+40 RT	6.2		6.2
STA. 48+21 LT	30.0		30.0
STA. 50+56 LT	30.0		30.0
STA. 51+75 LT	6.2		6.2
STA. 51+75 RT	6.2		6.2
STA. 53+59 LT TO STA. 54+25 LT		133.9	133.9
STA. 53+74 RT TO STA. 54+25 RT		96.5	96.5
STA. 56+75 LT	6.2		6.2
STA. 56+75 RT	6.2		6.2
STA. 58+75 LT	6.2		6.2
STA. 58+75 RT	6.2		6.2
STA. 60+80 LT TO STA. 61+44 LT		99.3	99.3
STA. 61+76 RT TO STA. 61+41 RT		216.3	216.3
STA. 64+44 LT	8.0		8.0
STA. 64+44 RT	8.0		8.0
STA. 47+42 LT TO STA. 48+13 RT		122.4	122.4
SUBTOTAL	243.9	995.6	1239.5
42ND STREET			
STA. 193+63 LT	6.2		6.2
STA. 194+95 LT	6.2		6.2
STA. 195+23 LT TO STA. 196+48 LT		679.4	679.4
STA. 196+25 RT TO STA. 197+22 RT		159.2	159.2
STA. 196+72 LT TO STA. 197+14 LT		144.6	144.6
STA. 198+25 RT	8.0		8.0
STA. 198+91 RT TO STA. 199+08 RT		89.7	89.7
STA. 200+59 RT TO STA. 200+93 RT		74.7	74.7
STA. 202+00 RT	14.7		14.7
STA. 193+63.55 RT	50.3		50.3
STA. 192+28.24 RT	50.3		50.3
SUBTOTAL	135.7	1147.6	1283.3
45TH STREET			
STA. 111+00 RT	16.3		16.3
SUBTOTAL	16.3		16.3
SEDIMENT BASINS FOR AGGREGATE (EROSION CONTROL)			
SUBTOTAL			395.6
GRAND TOTAL	395.9	2143.1	2934.3
USE TOTAL	396	2143	2934

TEMPORARY EROSION CONTROL SEEDING GRADE SEPARATION		
LOCATION	TEMPORARY EROSION CONTROL SEEDING	POUND
VETERANS MEMORIAL DRIVE		
STA. 36+50.00 TO STA. 48+00.00		308.0
STA. 51+50.00 TO STA. 61+00.00		275.0
STA. 62+60.00 TO STA. 76+40.34		118.0
SUBTOTAL		701.0
45TH STREET		
STA. 101+60.00 TO STA. 107+93.11		80.0
STA. 110+12.23 TO STA. 111+00.00		9.0
SUBTOTAL		89.0
42ND STREET		
STA. 192+24.27 TO STA. 195+00.00		37.0
STA. 197+00.00 TO STA. 199+00.00		75.0
STA. 201+00.00 TO STA. 207+32.15		39.0
SUBTOTAL		151.0
ACCESS ROAD #1		
STA. 5+40.82 TO STA. 15+38.00		49.0
SUBTOTAL		49.0
ACCESS ROAD #2		
STA. 20+79.50 TO STA. 22+00.00		18.0
SUBTOTAL		18.0
TEMPORARY ACCESS ROAD		
STA. 15+00.00 TO STA. 17+40.65		12.0
SUBTOTAL		12.0
ACCESS ROAD #2 - MISCELLANEOUS		
FIELD NORTH OF CANCER CENTER ROAD		68.0
NORTH EAST CORNER CANCER CNTR RD		8.0
NORTH WEST CORNER CANCER CNTR RD		7.0
SOUTH EAST CORNER CANCER CNTR RD		6.0
SOUTH WEST CRNR AND DRAINAGE DITCH		40.0
SUBTOTAL		129.0
INTERSECTION NEAR STA 35+00 VETERANS MEMORIAL DRIVE		
		41.0
SUBTOTAL		41.0
VETERANS MEMORIAL DRIVE BRIDGE OVER IL. RTE. 57 / 64		
		92.0
SUBTOTAL		92.0
INTERSECTION NEAR STA 61+50 VETERANS MEMORIAL DRIVE		
		9.0
SUBTOTAL		9.0
TOTAL		1317.0
USE TOTAL		1317

EROSION CONTROL BLANKET - GRADE SEPARATION		
LOCATION	EROSION CONTROL BLANKET	SQ YD
VETERANS MEMORIAL DRIVE		
LT STA. 36+69.00 TO LT STA. 43+42.00		1046.9
RT STA. 36+76.00 TO RT STA. 43+42.00		1036.0
LT STA. 45+28.00 TO LT STA. 45+65.00		57.6
LT STA. 41+50.00 TO LT STA. 59+50.00		3097.6
RT STA. 41+00.00 TO RT STA. 59+50.00		5323.9
RT STA. 45+48.00 TO RT STA. 45+65.00		26.4
RT STA. 46+25.00 TO RT STA. 48+21.00		304.9
LT STA. 46+25.00 TO LT STA. 48+30.00		318.9
LT STA. 50+84.00 TO LT STA. 53+59.00		427.8
RT STA. 51+75.00 TO RT STA. 53+74.00		309.6
LT STA. 56+25.00 TO LT STA. 61+76.00		857.1
RT STA. 56+44.00 TO RT STA. 60+80.00		678.2
LT STA. 62+70.00 TO LT STA. 70+00.00		1135.6
RT STA. 62+80.00 TO RT STA. 65+00.00		342.2
SUBTOTAL		14133.3
45TH STREET		
RT,LT STA. 101+50 TO RT,LT STA. 107+88.00		992.4
LT STA. 107+88.00 TO LT STA. 108+52.00		99.6
RT STA. 109+80.00 TO RT STA. 111+00.00		186.7
SUBTOTAL		1278.7
42ND STREET		
LT STA. 194+32.00 TO LT STA. 194+86.00		108.0
RT STA. 196+25.00 TO RT STA. 198+91.00		532.0
LT STA. 196+88.00 TO LT STA. 198+19.00		262.0
LT STA. 200+83.00 TO LT STA. 201+02.00		29.6
RT STA. 200+94.00 TO RT STA. 201+75.00		126.0
LT STA. 201+06.00 TO LT STA. 204+51.76		537.8
SUBTOTAL		1595.4
ACCESS ROAD #1		
RT STA. 14+50.00 TO RT STA. 15+50.00		155.6
SUBTOTAL		155.6
GRAND TOTAL		17162.9
USE TOTAL		17163

PERIMETER EROSION BARRIER - GRADE SEPARATION	
LOCATION	PERIMETER EROSION BARRIER FOOT
VETERANS MEMORIAL DRIVE	
RT STA. 36+13 TO RT STA. 43+18	724.0
RT STA. 45+00 TO RT STA. 48+00	300.0
LT STA. 45+00 TO LT STA. 47+95	295.0
RT STA. 51+48 TO RT STA. 54+25	277.6
LT STA. 51+48 TO LT STA. 54+07	258.7
RT STA. 65+11 TO RT STA. 76+40	1130.7
LT STA. 73+01 TO LT STA. 76+40	344.8
SUBTOTAL	3330.8
45TH STREET	
RT STA. 103+24 TO LT STA. 106+24	320.3
SUBTOTAL	320.3
RELOCATED GRAHAM ROAD	
RT STA. 201+75 TO RT STA. 209+15	847.7
SUBTOTAL	847.7
42ND STREET	
LT STA. 196+00 TO RT STA. 198+95	240.0
LT STA. 204+09 TO RT STA. 207+32	327.1
SUBTOTAL	567.1
ACCESS ROAD #1	
RT STA. 8+43 TO RT STA. 14+17	377.0
SUBTOTAL	377.0
GRAND TOTAL	5442.9
USE TOTAL	5443

EROSION CONTROL EXCAVATION SCHEDULE GRADE SEPARATION		
LOCATION	EARTH EXCAVATION FOR EROSION CONTROL CU YD	AGGREGATE (EROSION CONTROL) TON
LOCATION #1		
AS DETERMINED BY ENGINEER/CONTRACTOR	9.25	67.7
SUBTOTAL	9.25	67.7
LOCATION #2		
AS DETERMINED BY ENGINEER/CONTRACTOR	9.25	67.7
SUBTOTAL	9.25	67.7
GRAND TOTAL	18.5	135.4
USE TOTAL	20	136

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK SCALE: NO SCALE DATE 3-22-07
NAME	DATE	
DRAWN BY RL		CHECKED BY MTM
DATE 3-22-07		