

STORM SEWER SCHEDULES -- PIPES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	41-3)HBK	JEFFERSON	518	080
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

PIPE/CULVERT NUMBER (P# / C#)	FROM STRUCTURE (S#)	INVERT ELEV. (FT)	TO STRUCTURE (S#)	INVERT ELEV. (FT)	PIPE SLOPE %	STORM SEWERS, CLASS A, TYPE 1					PIPE CULVERTS					PIPE CULVERTS CL A 24" (JACKED)	PIPE DRAINS 12"	CONCRETE COLLAR	REINF. BARS	PRE. CONC. BOX CULV. 4' X 2'	PRE. CONC. BOX CULV. 6' X 3'	TRENCH BACKFILL	NOTES/REMARKS
						12" DIA.	15" DIA.	18" DIA.	24" DIA.	30" DIA.	TYPE 2 RCCP 36" DIA.	TYPE 3 RCCP 48" DIA.	TYPE 6 RCCP 48" DIA.	TYPE 6 RCCP 24" DIA.	TYPE 6 RCCP 36" DIA.								
VETERANS MEMORIAL DRIVE (CONTINUED)																							
P109	S12	503.07	S11	503.00	0.44	12.1															1.6		
P110	S132	500.57	S133	500.39	0.80		20.0														4.5		
P111	S133	500.39	S134	499.75	2.00																	NOTE 1	
P112	S135	501.15	S134	501.00	0.80	14.9															2.0		
P113	S9	506.52	S8	506.50	0.44	1.7															0.3		
P114	S6	508.38	S8	504.76	1.80																	NOTE 1	
P115	S8	504.76	S11	501.08	1.81																	NOTE 1	
P116	S11	501.08	S134	499.75	1.35																	NOTE 1	
P117	S134	499.75	S14	497.06	1.36																	NOTE 1	
P118	S14	497.06	S23	495.65	0.56																	NOTE 1	
P119	S23	495.65	S137	495.04	1.11																	NOTE 1	
P120	S138	511.51	S139	510.59	2.90																	NOTE 1	
P121	EXIST.	510.07	S152	510.00	2.0														4				
P125	S25	494.13	S137	494.04	0.08							103.0									47.2		
P126	S137	494.03	S26	493.99	0.08							56.0									19.6		
SUBTOTAL						473.4	68.6	73.7	36.0			115	159	166	183	480			1471.0	19.5	1820.0	4	452.2
42ND STREET																							
C8	S54	489.97	S55	489.11	0.83							94									41.9		
P17	S27	499.34	S28	499.09	1.00														25.0			0.3	
P18	S29	498.96	S30	498.85	1.10	8.2															1.1		
P19	S30	498.07	S32	497.75	0.80	36.1															4.8		
P20	S39	507.84	S40	507.60	0.80	27.1															3.7		
P21	S40	507.57	S41	507.50	0.80	6.5															0.5		
P22	S41	504.86	S38	502.00	2.27																	NOTE 1	
P23	S36	504.51	S37	504.10	1.30	28.4															3.7		
P24	S37	504.07	S38	504.00	0.80	6.1															0.3		
P25	S38	502.00	S35	499.37	1.31																	NOTE 1	
P26	S34	500.47	S35	498.33	1.00	44.9															5.9		
P27	S35	497.76	S127	497.50	0.26			96.0													12.5		
P28	S31	497.37	S32	497.35	0.22			8.2													0.9		
P29	S32	497.13	S163	496.88	0.22				49.6												0.9		
P30	S44	498.27	S45	490.75	33.33														34.3		0.3		
P31	S46	498.03	S47	492.25	33.33														28.1	0.3	28	0.4	
P32	S48	496.28	S49	490.08	33.33														29.8			0.3	
P33	S50	496.51	S51	491.71	33.33														28.3			0.3	
P34	S58	493.14	S59	492.94	0.80	40.0															5.0		
P35	S59	492.84	S60	492.55	0.80	7.1															1.7		
P36	S63	491.41	S62	491.15	0.47	40.0															6.9		
P37	S62	490.79	S61	490.75	0.48	22.0															0.3		
P103	S127	497.55	S31	497.45	0.26			34.8													3.7		
P124	S163	496.78	S33	496.75	0.23				7.0														
P132	S167	491.36	S63	491.17	0.25	7.0																	
SUBTOTAL						273.3		139.0	56.6			94							145.5	0.3	28.0	56.0	95.4

CONTINUED ON NEXT SHEET

NOTE 1 - EXISTING PIPE TO REMAIN IN PLACE, CONTRACTOR SHALL CLEAN PIPE IF NECESSARY.



03/21/2007 07:41 AM I:\98\hbs\98\98\road\sheet\605-disc.dgn

LAYOUT	RLT	02/26/04
DRAWN	HEJ	04/12/04
REVIEWED	MTM	03/22/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE SCHEDULE
VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK
SCALE: NO SCALE
DATE 3-22-07
DRAWN BY RLT
CHECKED BY MTM