

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	082
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

DRAINAGE SCHEDULE - RAMPS

LOCATION STATION TO STATION	PIPE CULVERT, CLASS A, TYPE 5, 24"	PIPE CULVERT, CLASS A, TYPE 1, 24"	PIPE CULVERTS, CLASS A, TYPE 1, EQUIVALENT ROUND-SIZE, 36"	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION-ELLIPTICAL, EQUIVALENT ROUND SIZE, 36"	CONCRETE COLLAR	COMB. CURB AND GUTTER TYPE M-6.24	COMB. CURB AND GUTTER TYPE M-6.06	COMB. CURB AND GUTTER TYPE B-6.24	CONCRETE MEDIAN SURFACE, 4"	PROTECTIVE COAT	TRENCH BACKFILL
	FOOT	FOOT	FOOT	EACH	EACH	CU YD	FOOT	FOOT	FOOT	SQ FT	SQ YD	CU YD
I-57/I-64 749+00(93.57' LT)		12		1		0.44						
RAMP A												
300+50.0 (51.5' LT) TO 300+99.3 (20.8' RT)									59.2		17.0	
300+50.0 (76.3' RT) TO 301.19.0 (3.2' RT)									133.6		38.3	
RAMP B												
411+00			43.0									23.3
411+00 (14.0' RT)					1							
411+00 (29.0' LT)					1							
420+67.4 (2.7' RT) TO 421+45.0 (136.2' RT)										164.4		47.1
421+07.9 (17.1' LT) TO 421+38.7 (28.4' LT)									33.0		9.5	
421+33.5 (ISLAND)							78.7	46.3		128.2	43.5	
RAMP C												
500+15.8 (76.3' RT) TO 501+19.0 (3.2' RT)										133.6		38.3
500+50.0 (51.5' LT) TO 500+99.7 (20.8' LT)									59.6		17.1	
503+50	156.0											9.2
503+50 (84.0' LT)					1							
503+50 (72.0' RT)					1							
RAMP D												
616+74.0 (2.7' RT) TO 617+52.1 (135.2' RT)										163.7		46.9
617+13.1 (17.2' LT) TO 617+44.3 (28.8' LT)									33.5		9.6	
617+39.1 (ISLAND)							73.4	47.7		121.4	41.5	
TOTALS	156	12	43	3	2	0.4	153	94	781	250	310	32.5

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/21/2007 07:41 AM
 I:\98\pds\98s2019a\road\steelAc-607-dsca.dgn

LAYOUT	RLT	02/26/04
DRAWN	JED	04/12/04
REVIEWED	MJM	03/22/07

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK SCALE: NO SCALE DATE 3-22-07
NAME	DATE	

DRAWN BY RLT
 CHECKED BY MTM