DK051

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR107408	L-806 WIND CONE-8' LIGHTED	EA.	1	
AR110014	4" DIRECTIONAL BORE	L.F.	426	
AR125907	REMOVE REILS	PR.	1	
AR127420	GLIDE SLOPE	L.S.	1	
AR127431	10' X 12' SHELTER BUILDING	EA.	1	
AR127432	10' X 14' SHELTER BUILDING	EA.	1	
AR127450	MALSR INSTALLATION	L.S.	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	177	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	371	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	17,152	
AR620912	TEMPORARY MARK & LIGHT	L.S.	1	
AR800432	TELEPHONE CABLE	L.F.	1,964	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION	DRAWING NUMBER
1	COVER SHEET	
2	SUMMARY OF QUANTITIES, INDEX TO SHEETS	
3	PROPOSED SAFETY PLAN	
4	PROPOSED TEMPORARY MARKING AND LIGHTING PLAN	
5	PROPOSED RUNWAY 2-20 MARKING PLAN	
6	PROPOSED UTILITY PLAN	
7	ELECTRICAL LEGEND AND ABBREVIATIONS	
8	SUMMARY OF QUANTITIES FOR MALSR INSTALLATION	
9	RUNWAY 2 MALSR PLAN & PROFILE STA. 90+00 TO STA. 102+00	DKB-D-MALSR02-C01
10	RUNWAY 2 MALSR PLAN & PROFILE STA. 78+00 TO STA.90+00	DKB-D-MALSR02-C02
11	RUNWAY 2 MALSR SHELTER SITE PLAN	DKB-D-MALSR02-C03
12	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BAR AT RUNWAY THRESHOLD	DKB-D-MALSR02-C04
13	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BAR AT STATION 2+10 RUNWAY 02	DKB-D-MALSR02-C05
14	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BAR AT STATION 4+20 RUNWAY 02	DKB-D-MALSR02-C06
15	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BAR AT STATION 6+30 AND 8+40 RUNWAY 02	DKB-D-MALSR02-C07
16	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BARS AT STATION 10+50 RUNWAY 02	DKB-D-MALSR02-C08
17	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BAR AT STATION 12+50 RUNWAY 02	DKB-D-MALSR02-C09
18	MALSR FOUNDATION DETAILS FOR STEADY-BURNING LIGHT BAR AT STATION 14+50 RUNWAY 02	DKB-D-MALSR02-C10
19	MALSR FOUNDATION DETAILS FOR FLASHER AT STATIONS 16+40 THRU 20+20 RUNWAY 02	DKB-D-MALSR02-C11
20	MALSR FOUNDATION DETAILS FOR FLASHER AT STATIONS 22+10 AND 24+00 RUNWAY 02	DKB-D-MALSR02-C12
21	MALSR CRUSHED ROCK PLOT DETAILS	DKB-D-MALSR02-C13
22	MALSR MISCELLANEOUS DETAILS RUNWAY02	DKB-D-MALSR02-C14
23	MALSR STRUCTURE ASSEMBLY DETAILS FOR LIR TOWER, TYPE MG-20 RUNWAY 02	DKB-D-MALSR02-S01
24	MALSR STRUCTURE ASSEMBLY DETAILS FOR LIR TOWER, TYPE MG-30 AND MG-40 RUNWAY 02	DKB-D-MALSR02-S02
25	MALSR FOUNDATION, FRAMING AND LIGHTNING PROTECTION DETAILS FOR 10' X 12' WOOD FRAME EQUIPMENT SHELTER RUNWAY 02	DKB-D-MALSR02-A01
26	MALSR FLOOR PLAN AND INTERIOR ELEVATIONS 10' X 12' WOOD FRAME EQUIPMENT SHELTER RUNWAY 02	DKB-D-MALSR02-A02
27	MALSR SYSTEM WIRING DIAGRAM RUNWAY 02	DKB-D-MALSR02-E01
28	MALSR EQUIPMENT WIRING DIAGRAM FOR TYPE FA-9994 RUNWAY 02	DKB-D-MALSR02-E02
28A	MALSR EQUIPMENT WIRING DIAGRAM FOR TYPE FA-11501 RUNWAY 02	DKB-D-MALSR02-E02
29	MALSR WIRING DIAGRAMS FOR STEADY-BURNING LIGHT BARS RUNWAY 02	DKB-D-MALSR02-E03
30	MALSR LIGHT MOUNTING DETAILS RUNWAY 02	DKB-D-MALSR02-E04
31	MALSR ELECTRICAL ONE LINE, RUNWAY 02	DKB-D-MALSR02-E05
32	MALSR PANEL SCHEDULES RUNWAY 02	DKB-D-MALSR02-E06
32A	MULTI ELECTRIC RAIL DETAILS	DKB-D-MALSR02-E07
33	SUMMARY OF QUANTITIES FOR GLIDE SLOPE INSTALLATION	
34	GLIDE SLOPE PROPOSED SITE PLAN RUNWAY 02	DKB-D-GS02-C01
35	GLIDE SLOPE ANTENNA TOWER FOUNDATION DETAILS RUNWAY 02	DKB-D-GS02-C02
36	GLIDE SLOPE ANTENNA TOWER ASSEMBLY DETAILS RUNWAY 02	DKB-D-GS02-S01
37	GLIDE SLOPE FOUNDATION AND FRAMING DETAILS 10' X 14' WOOD FRAME EQUIPMENT SHELTER RUNWAY 02	DKB-D-GS02-A01
38	GLIDE SLOPE FLOOR PLAN AND INTERIOR ELEVATIONS 10' X 14' WOOD FRAME EQUIPMENT SHELTER RUNWAY 02	DKB-D-GS02-A02
39	GLIDE SLOPE ANTENNA TOWER ELECTRICAL AND GROUNDING DETAILS RUNWAY 02	DKB-D-GS02-E01
40	GLIDE SLOPE ELECTRICAL ONE LINE RUNWAY 02	DKB-D-GS02-E02
41	ILS/ALS EQUIPMENT SHELTERS LIGHTNING PROTECTION AND ELECTRONIC GROUNDING PLATE DETAILS RUNWAY 02	DKB-D-ILS/ALS02-E01
42	UTILITY TRANSFORMER PAD DETAIL	
43	ELECTRICAL DETAILS 1	
44	ELECTRICAL DETAILS 2	
45	ELECTRICAL NOTES SHEET 1	
46	ELECTRICAL NOTES SHEET 2	
47	GROUNDING DETAILS	
48	GROUNDING NOTES	
48A	PROPOSED WIND CONE ON RUNWAY END 2	
48B	WIND CONE DETAILS	

DATE	REVISION	BY

DMA

DEKALB TAYLOR MUNICIPAL AIRPORT

IL. PROJ.: DKB-3225 A.I.P. PROJ.: 3-17-0139-B37

HANSON PROJECT No. 803-06ELEC

Filename: R-001FLP.DWG

Scale: NOT TO SCALE

Date: 06/27/07

LAYOUT	BAK	02/02/07
DRAWN	BAK	02/02/07
REVIEWED	CAH	03/19/07

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

INSTALL MALSR & GLIDE SLOPE

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

2

JUL 25, 2007 9:35 AM BAK
N:\AIRPORTS\DEKALB\803-06ELEC\AIRPORT\SHEETS\AUTO-CADD SHEETS\R-001FLP.DWG - Layout1