

TREE REMOVAL, ACRES	
LOCATION	ACRES
0+35 - 1+53 LT	0.02
1+71 - 4+66 LT	0.18
7+27 - 10+40 LT	0.09
11+94 - 12+52 RT	0.03
TOTAL	0.32

SEEDING & EROSION CONTROL SCHEDULE									
LOCATION	SEEDING, MULCHING & FERTIL.	SEEDING, & FERTIL.	TEMPORARY EROSION CONTROL SEEDING	TURF REIN-FORCEMENT MAT	HEAVY DUTY EROSION CONTROL BLANKET	SEEDING, CLASS 4B	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
		ACRE	POUND	SQ YD	SQ YD				
0+16 - 11+95 LT		0.20	10	1,146					
0+08 - 11+95 RT		0.24	12	992					
WETLAND BERM		0.29	14		768				
WETLAND CHANNEL CONNECTION AREA 8+66.24			4		362	0.08	10	10	10
6+98 RT DIVERSION TRENCH #1	0.10		5						
12+34 RT DIVERSION TRENCH #2	0.08		4						
HAUL ROAD & CONSTRUCTION ENTRANCE AT JC POND	0.42		21						
CONSTRUCTION ENTRANCE TO WETLANDS NORTH OF RIVER STREET	0.07		4						
CONSTRUCTION ENTRANCE TO SPOIL SITE SOUTH OF RIVER STREET	0.02		1						
TOTAL	0.69	0.73	75	2,138	1,130	0.08	10	10	10

STONE RIPRAP, CLASS A5 & FILTER FABRIC		
LOCATION	SIDESLOPES	SQ YD
	LT 3+95-7+44	493
	LT 7+92-11+47	731
	RT 3+95-7+44	444
	RT 7+92-11+47	626
TOTAL		2,294

TREE PLANTINGS			
LOCATION			
	AROUND JC PARK POND	WETLAND AREA SOUTH OF BLACKBERRY CREEK	TOTAL
KENTUCKY COFFEE TREE	3		3
SYCAMORE	2		2
BURR OAK	3	4	7
SUGAR MAPLE	3	5	8
RED OAK		4	4
PIN OAK		4	4
COLORADO BLUE SPRUCE		3	3

STONE RIPRAP, CLASS A7 & FILTER FABRIC	
LOCATION	SQ YD
RIFFLE #1	293
RIFFLE #2	293
RIFFLE #3	293
LT 0+10 - 3+47	441
RT 0+08 - 3+47	435
TOTAL	1,755

SCHEDULE OF EARTHWORK					
LOCATION	CHANNEL EXCAVATION CU YD	ROCK EXCAVATION IN CHANNEL CU YD	EMBANKMENT CU YD	6" TOPSOIL PLACEMENT FROM ONSITE STOCKPILED MATERIAL	EARTH EXCAVATION (SURPLUS OF STOCKPILED MATL. TO BE DISPOSED OF) CU YD
0+13 - 11+95	10,868				
0+35.5 - 11+95			763		
0+08 - 11+95				576	
6+98 RT DIVERSION TRENCH #1	405				
WETLAND CHANNEL CONNECTION AREA 8+66.24	1,200				
12+34 RT DIVERSION TRENCH #2	460				
HAUL ROAD & CONSTRUCTION ENTRANCE AT JC POND					
CONSTRUCTION ENTRANCE TO WETLANDS NORTH OF RIVER STREET					
CONSTRUCTION ENTRANCE TO SPOIL SITE SOUTH OF RIVER STREET				544	
PHASE I SPOIL SITES AT J C POND AND YBSD PROPERTY SOUTH OF RIVER ROAD					1,274
RIFFLE LOCATIONS (Riffle toes only)		23			
0+00-11+95 TOE IN FOR CHANNEL RIPRAP		841			
TOTAL	12,933	864	763	1,120	1,274

MASONRY REMOVAL AND DISPOSAL	
LOCATION	CU YD
0+02 - 0+19	273

MASONRY REMOVAL AND STOCKPILE	
LOCATION	CU YD
0+02 - 0+19	273

CA-3 HAUL ROAD REMOVAL (NOT A PAY ITEM)	
LOCATION	CU YD
HAUL ROAD AND CONSTRUCTION ENTRANCES AT JC POND, WETLANDS AREA, AND SPOIL SITE SOUTH OF RIVER STREET	544
TOTAL	544