

FILE NAME * S:\JUL162008-62991\6346\023\Micro\54\1\018012-1\11111111.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE												
				80% FED. 20% STATE	80% STATE 20% MONT-GOMERY	80% STATE 20% OSWEGO	80% FED. 20% STATE BRIDGE REPLACEMENT S. N. 047-0301	80% FED. 10% STATE 5% MONT-GOMERY 5% OSWEGO TOWNSHIP BRIARCLIFF	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY DOUGLAS	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY FIFTH	100% MONT-GOMERY GOODWIN DR.	50% OSWEGO 50% MONT-GOMERY STREET LIGHTING	80% FED. 20% STATE NOISE ABATEMENT WALLS	80% FED. 20% STATE WATER MAIN	100% OSWEGO	
				ROADWAY 0003	SIDEWALK 0021	SIDEWALK 0021	0010	TRAFFIC SIGNALS - 0021					0021	0040	0043	0043
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
K0012970	PERENNIAL PLANTS, BULB TYPE	UNIT	25.5	25.5												
K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	22.64	22.64												
+ K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	30	30												
+ X0301423	NOISE ABATEMENT WALL, GROUND MOUNTED	SO FT	171,237	171,237												
+ X0323003	TEMPORARY ELECTRIC SERVICE INSTALLATION	EACH	1								1					
+ X0324097	COARSE SAND PLACEMENT, 2"	SO YD	412	412												
X0326160	POROUS GRANULAR EMBANKMENT, SUBGRADE (SPECIAL)	CU YD	100									100				
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	432				432									
X2080250	TRENCH BACKFILL, SPECIAL	CU YD	20									20				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3												
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4												
X4201000	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SO YD	1,739	1,739												
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	285	285												
△ X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	222	222												

+ SPECIALTY ITEM • 100% OSWEGO

△ 100% STATE

△ Rev. 9-10-12

Rev.



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
18151 744-4200
PLOT SCALE = 20.0000' / 1" = 100'
PLOT DATE = 5/14/2012

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	11 WRS-3	KENDALL	527	28
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60132	