

SCHEDULE OF PAVEMENT MARKINGS

FROM STATION	TO STATION	OFFSET	DESCRIPTION	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (SO FT) 78000100	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (FOOT) 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 6" (FOOT) 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 12" (FOOT) 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 24" (FOOT) 78000650	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS (SO FT) 78008200	POLYUREA PAVEMENT MARKING TYPE I - LINE 4" (FOOT) 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 6" (FOOT) 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 8" (FOOT) 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 12" (FOOT) 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 24" (FOOT) 78008270	RAISED REFLECTIVE PAVEMENT MARKER (EACH) 78100100	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH) 78100105	REPLACEMENT REFLECTOR (EACH) 78100300	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH) 78300200
435+41	438+17	LT	6SW								275							
435+41	435+43	RT/LT	24SW										44					
435+53	435+53	RT						34.6										
437+00	444+72	LT	4SDW						240									
437+81	437+81	RT						34.6										
438+39	443+55	RT	6SDW							129								
438+39	444+72	RT/LT															34	34
438+40	441+79	LT	4SW						359									
439+40	441+17	LT	12SW									48						
440+00	440+00	LT						34.6										
441+55	442+46	LT	8SW								230							
441+55	442+46	LT	12SW									47						
441+68	441+78	RT/LT	24SW										13					
442+45	444+72	LT	4SW							227								
442+46	444+72	LT	6SW							226								
442+67	442+67	LT						34.6										
443+55	444+72	RT	6SW							117								
443+55	444+72	RT	6SW							117								
443+67	443+67	RT						34.6										
443+67	443+67	RT						34.6										
DOUGLAS RD.																		
204+35	205+69	RT	6SW			134												
204+35	205+51	LT	6SW			116												
204+35	208+88	RT/LT															33	33
204+46	204+46	RT		36.4														
204+52	205+82	LT	4SDW		40													
204+57	205+69	RT	4SDW		30													
205+38	205+38	LT		36.4														
205+69	205+69	RT	24SW					45										
206+51	208+62	RT	4SDW		60													
206+54	206+54	LT	24SW					36										
206+56	207+72	LT	6SW			115												
206+82	208+88	LT	4SDW		60													
207+57	207+57	LT		36.4														
208+88	209+71	LT	4SDW							20								
208+88	209+95	RT	4SDW							30								
208+88	209+97	RT	6SW								107							
208+88	213+20	N/A												18				
209+00	209+00	LT						34.6										
209+80	209+82	LT	24SW										14					
209+95	209+97	RT	24SW										29					
210+00	210+06	RT/LT	6SW								187							
211+47	212+33	LT	6SW								86							
211+47	211+49	LT	24SW										26					
211+49	213+20	LT	4SDW							40								
211+49	213+20	RT	4SDW							40								
211+62	211+64	RT/LT	24SW										12					
212+00	212+00	LT						34.6										
213+20	214+69	RT	4SDW		40													
213+20	214+57	LT	4SDW		40													
213+20	214+66	LT	4DY		292													
213+20	219+26	N/A															36	36
213+69	214+66	RT	6SW			96												
213+74	213+74	LT		36.4														
215+52	216+52	LT	6SW			100												
215+60	219+26	RT	4SDW		100													
215+60	219+26	LT	4SDW		100													
215+60	219+26	RT/LT	4DY		1157													
SUBTOTAL				146	1919	561	0	81	277	956	1244	230	95	138	18	0	103	103

FILE NAME = S:\JOL\63300-63999\6346-023\Microa\CADD Sheets\0160132-sht-schedule.dgn



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = amandaj	DESIGNED -	REVISED -
	PLOT SCALE = 48.0000' / in.	DRAWN -	REVISED -
	PLOT DATE = 8/6/2012	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	11 WRS-3	KENDALL	527	63
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60132	