

CODE NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 0003		BRIDGE 0013	TRAFFIC SIGNALS 0021				LIGHTING 0021		RETAINING WALL 0040	
				KANE COUNTY	KENDALL COUNTY		IL 31 AT EB US 30 RAMP		IL 31 AT WB US 30 RAMP	US 30 AT RAMP	IL 31 INTERCONNECT	KANE COUNTY		KENDALL COUNTY
							KANE COUNTY	VILLAGE OF MONTGOMERY						
				80% FED 20% STATE	80% FED 20% STATE		80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE		80% FED 20% STATE
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5087	2031	2256									
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	605	605										
40701931	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12 1/2"	SQ YD	10,452	10,452										
40701936	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12 3/4"	SQ YD	14,988	14,988										
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	494	391	103									
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	197	197										
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	52	52										
44000100	PAVEMENT REMOVAL	SQ YD	37,626	36,247	1379									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1425	1425										
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,393	6,393										
44003100	MEDIAN REMOVAL	SQ FT	39,952	33,477	6,475									
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	51	34	17									
44201299	DOWEL BARS 1 1/2"	EACH	60	40	20									
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	3,931	1,887	2,044									
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	387	185	202									
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	673	395	278									
44213200	SAW CUTS	FOOT	144	96	48									
44213208	TIE BARS 1 1/4"	EACH	60	40	20									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	23,923	12,605	11,318									
48101600	AGGREGATE SHOULDERS, TYPE B, 8"	SQ YD	3558	2768	790									

FILES 5/23/2012 3:59:19 PM

USER NAME * 165*	DESIGNED - JWB	REVISED -
PLOT SCALE * 180.0000 "/ IN.	DRAWN - JWB	REVISED -
PLOT DATE * 5/23/2012	CHECKED - RS	REVISED -
	DATE - 05/23/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31  
SUMMARY OF QUANTITIES

SHEET NO. 500-3 OF 19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3		507	6
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				

Rev. 9-13-12

Rev.