

FROM	TO	20200100									20400800								
		EARTH EXCAVATION			EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT			EMBANKMENT			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION			WASTE HAUL OFF		
		CU YD			CU YD			CU YD			CU YD			CU YD			CU YD		
STATION	STATION	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage
Infields																			
N. E. Infield			34846		0	29619	0		14273		0	15346	0	0	0	0	0	15346	0
S. E. Infield		26517			22539	0	0	9465			13074	0	0	0	0	0	13074	0	0
Two S. W. Infields		5740			4879	0	0	2934			1945	0	0	0	0	0	1945	0	0
N. W. Infield			14453		0	12285	0		12830	1796	0	-545	-1796	0	545	1796	0	0	0
Ramp A																			
301+50	302+00		219		0	186	0		333		0	-147	0	0	147	0	0	0	0
302+00	302+50		177		0	150	0		406		0	-256	0	0	256	0	0	0	0
302+50	303+00		91		0	77	0		589		0	-512	0	0	512	0	0	0	0
303+00	303+50		50		0	43	0		697		0	-655	0	0	655	0	0	0	0
303+50	304+00		73		0	62	0		691		0	-629	0	0	629	0	0	0	0
304+00	304+50		51		0	43	0		741		0	-698	0	0	698	0	0	0	0
304+50	305+00		33		0	28	0		736		0	-708	0	0	708	0	0	0	0
305+00	305+50		73		0	62	0		640		0	-578	0	0	578	0	0	0	0
305+50	306+00																		
306+00	306+50		130		0	111	0		1113		0	-1003	0	0	1003	0	0	0	0
306+50	307+00		19		0	16	0		643		0	-627	0	0	627	0	0	0	0
307+00	307+50		45		0	38	0		910		0	-872	0	0	872	0	0	0	0
307+50	308+00		96		0	82	0		1258		0	-1176	0	0	1176	0	0	0	0
308+00	308+50		233		0	198	0		1241		0	-1043	0	0	1043	0	0	0	0
308+50	309+00		422		0	359	0		796		0	-437	0	0	437	0	0	0	0
309+00	309+50		452		0	384	0		418		0	-34	0	0	34	0	0	0	0
309+50	310+00		466		0	396	0		191		0	205	0	0	0	0	0	205	0
310+00	310+50		568		0	483	0		77		0	406	0	0	0	0	0	406	0
310+50	311+00		640		0	544	0		58		0	486	0	0	0	0	0	486	0
311+00	311+50		687		0	584	0		33		0	551	0	0	0	0	0	551	0
311+50	312+00		658		0	559	0		23		0	536	0	0	0	0	0	536	0
312+00	312+50		509		0	433	0		43		0	390	0	0	0	0	0	390	0
312+50	313+00		345		0	293	0		77		0	216	0	0	0	0	0	216	0
313+00	313+50		210		0	179	0		102		0	77	0	0	0	0	0	77	0
313+50	314+00		122		0	104	0		92		0	12	0	0	0	0	0	12	0
314+00	314+50		86		0	73	0		73		0	0	0	0	0	0	0	0	0
314+50	315+00		36		0	31	0		33		0	-2	0	0	2	0	0	0	0
Ramp B																			
403+00	403+50		60		0	51	0		1900		0	-1849	0	0	1849	0	0	0	0
403+50	404+00				0	0	0		2312		0	-2312	0	0	2312	0	0	0	0
404+00	404+50				0	0	0		2280		0	-2280	0	0	2280	0	0	0	0

P:\Jobs\2012\03\031\04\01\Site\ent-schedule-for-thwork.dgn
 9/13/2012 3:29:56 PM



USER NAME - 1654	DESIGNED - JWB	REVISED - GRAEF 09/11/2012/1
	DRAWN - JWB	REVISED -
PLOT SCALE - 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE - 9/13/2012	DATE - 06/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31 EARTHWORK SCHEDULES	
SCALE: N.T.S.	SHEET NO. 1 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VBI) R-3	-	507	42
- KANE AND KENDALL			CONTRACT NO. 60133	
[ILLINOIS] FEO, AID PROJECT				