

FROM	TO	20200100						20400800												
		EARTH EXCAVATION			EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT			EMBANKMENT			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION			WASTE HAUL OFF			
		CU YD			CU YD			CU YD			CU YD			CU YD						
STATION	STATION	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	
404+50	405+00				0	0	0		2043		0	-2043	0	0	2043	0	0	0	0	0
405+00	405+50				0	0	0		1580		0	-1580	0	0	1580	0	0	0	0	0
405+50	406+00				0	0	0		701		0	-701	0	0	701	0	0	0	0	0
406+00	406+50				0	0	0		457		0	-457	0	0	457	0	0	0	0	0
406+50	407+00				0	0	0		730		0	-730	0	0	730	0	0	0	0	0
407+00	407+50		0		0	0	0		719		0	-719	0	0	719	0	0	0	0	0
407+50	408+00																			
408+00	408+50		0		0	0	0		1505		0	-1505	0	0	1505	0	0	0	0	0
408+50	409+00				0	0	0		787		0	-787	0	0	787	0	0	0	0	0
409+00	409+50				0	0	0		765		0	-765	0	0	765	0	0	0	0	0
409+50	410+00				0	0	0		702		0	-702	0	0	702	0	0	0	0	0
410+00	410+50				0	0	0		796		0	-796	0	0	796	0	0	0	0	0
410+50	411+00				0	0	0		759		0	-759	0	0	759	0	0	0	0	0
411+00	411+50				0	0	0		593		0	-593	0	0	593	0	0	0	0	0
411+50	412+00				0	0	0		554		0	-554	0	0	554	0	0	0	0	0
412+00	412+50				0	0	0		523		0	-523	0	0	523	0	0	0	0	0
Ramp C																				
501+00	501+50	0			0	0	0	337			-337	0	0	337	0	0	0	0	0	0
501+50	502+00	0			0	0	0	457			-457	0	0	457	0	0	0	0	0	0
502+00	502+50	0			0	0	0	579			-579	0	0	579	0	0	0	0	0	0
502+50	503+00	0			0	0	0	710			-710	0	0	710	0	0	0	0	0	0
503+00	503+50	0			0	0	0	946			-946	0	0	946	0	0	0	0	0	0
503+50	504+00	0			0	0	0	778			-778	0	0	778	0	0	0	0	0	0
504+00	504+50	0			0	0	0	421			-421	0	0	421	0	0	0	0	0	0
504+50	505+00	0			0	0	0	772			-772	0	0	772	0	0	0	0	0	0
505+00	505+50	0			0	0	0	1310			-1310	0	0	1310	0	0	0	0	0	0
505+50	506+00	0			0	0	0	1450			-1450	0	0	1450	0	0	0	0	0	0
506+00	506+50	4			3	0	0	903			-900	0	0	900	0	0	0	0	0	0
506+50	507+00	98			83	0	0	218			-135	0	0	135	0	0	0	0	0	0
Ramp D																				
603+50	604+00	135			115	0	0	156			-41	0	0	41	0	0	0	0	0	0
604+00	604+50	105			89	0	0	147			-58	0	0	58	0	0	0	0	0	0
604+50	605+00	179			152	0	0	100			52	0	0	0	0	0	52	0	0	0
605+00	605+50	227			193	0	0	100			93	0	0	0	0	0	93	0	0	0
605+50	606+00	174			148	0	0	251			-103	0	0	103	0	0	0	0	0	0
606+00	606+50	109			93	0	0	519			-426	0	0	426	0	0	0	0	0	0
606+50	607+00	56			48	0	0	641			-593	0	0	593	0	0	0	0	0	0



G:\Jobs\2010\201003\003\CAD\Site\Drawn\00\016033-sht-Schedule-Earthwork.dgn
 07/13/2012 3:26:11 PM

USER NAME * 1654	DESIGNED - JWB	REVISED - CRAEF 09/11/2012/1
PLOT SCALE * 100.0000' / IN.	DRAWN - JWB	REVISED -
PLOT DATE * 9/13/2012	CHECKED - RS	REVISED -
	DATE - 06/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
EARTHWORK SCHEDULES
 SCALE: N.T.S. SHEET NO. 2 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	43
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				