

FROM	TO	20200100						EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT	EMBANKMENT			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			20400800			WASTE HAUL OFF		
		EARTH EXCAVATION			CU YD				CU YD			CU YD			FURNISHED EXCAVATION			CU YD		
		STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage		STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage
607+00	607+50	64			54	0	0	324			-270	0	0	270	0	0	0	0	0	
607+50	608+00				0	0	0	148			-148	0	0	148	0	0	0	0	0	
608+00	608+50	11			9	0	0	181			-172	0	0	172	0	0	0	0	0	
608+50	609+00	85			72	0	0	180			-108	0	0	108	0	0	0	0	0	
609+00	609+50	21			18	0	0	228			-210	0	0	210	0	0	0	0	0	
IL 31																				
116+50	119+50		144		0	122	0		0		0	122	0	0	0	0	0	122	0	
119+50	121+50		0																	
121+50	123+00		93		0	79	0		139		0	-60	0	0	60	0	0	0	0	
123+00	124+50		204		0	173	0		623		0	-450	0	0	450	0	0	0	0	
124+50	129+17		735																	
129+17	129+50		45		0	38	0		15		0	23	0	0	0	0	0	23	0	
129+50	130+00		49		0	42	0		34		0	8	0	0	0	0	0	8	0	
130+00	131+50		65		0	55	0		97		0	-42	0	0	42	0	0	0	0	
131+50	133+50		0		0	0	0		111		0	-111	0	0	111	0	0	0	0	
133+50	134+00		0		0	0	0		10		0	-10	0	0	10	0	0	0	0	
US 30																				
1238+00	1238+50	16	9		14	8	0	0	0		14	8	0	0	0	0	14	8	0	
1238+50	1239+00	25	2		21	2	0	2	2		19	0	0	0	0	0	19	0	0	
1239+00	1239+50	31	3		26	3	0	2	6		24	-3	0	0	3	0	24	0	0	
1239+50	1240+00	40	9		34	8	0	3	11		31	-3	0	0	3	0	31	0	0	
1240+00	1240+50	82	16		70	14	0	4	18		66	-4	0	0	4	0	66	0	0	
1240+50	1241+00	187	71		159	60	0	1	11		158	49	0	0	0	0	158	49	0	
1241+00	1241+50	188	75		160	64	0	4	17		156	47	0	0	0	0	156	47	0	
1241+50	1242+00	121	40		103	34	0	12	38		91	-4	0	0	4	0	91	0	0	
1242+00	1242+50	69	44		59	37	0	27	46		32	-9	0	0	9	0	32	0	0	
1242+50	1243+00	22	47		19	40	0	28	45		-9	-5	0	9	5	0	0	0	0	
1243+00	1243+50	23	55		20	47	0	15	37		5	10	0	0	0	0	5	10	0	
1243+50	1244+00	29	75		25	64	0	5	31		20	33	0	0	0	0	20	33	0	
1244+00	1244+50	219	107		186	91	0	1	25		185	66	0	0	0	0	185	66	0	
1244+50	1245+00	481	109		409	93	0	0	22		409	71	0	0	0	0	409	71	0	
1245+00	1245+50	524	88		445	75	0	0	21		445	54	0	0	0	0	445	54	0	
1245+50	1246+00	476	72		405	61	0	0	18		405	43	0	0	0	0	405	43	0	
1246+00	1246+50	500	71		425	60	0	1	16		424	44	0	0	0	0	424	44	0	
1246+50	1247+00	559	78		475	66	0	1	16		474	50	0	0	0	0	474	50	0	
1247+00	1247+50	537	87		456	74	0	0	9		456	65	0	0	0	0	456	65	0	



P:\Jobs\2010\20103003\CAD\Site\Drawn\00\06033-ent-Schedule-Earthwork.dgn
 3/13/2012 3:50:21 PM

USER NAME - 1654	DESIGNED - JWB	REVISED - GRAEF 09/11/2012/1
	DRAWN - JWB	REVISED -
PLOT SCALE - 100.0000' / IN.	CHECKED - AS	REVISED -
PLOT DATE - 9/13/2012	DATE - 06/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31 EARTHWORK SCHEDULES	
SCALE: N.T.S.	SHEET NO. 3 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 V8) R-3	-	607	44
KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				