

FROM	TO	20200100						20400800											
		EARTH EXCAVATION			EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT			EMBANKMENT			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION			WASTE HAUL OFF		
		CU YD			CU YD			CU YD			CU YD			CU YD					
STATION	STATION	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage
1266+00	1266+50	123	66		105	56	0	98	520		7	-464	0	0	464	0	7	0	0
1266+50	1267+00	97	63		82	54	0	139	647		-57	-593	0	57	593	0	0	0	0
1267+00	1267+50	78	68		66	58	0	141	347		-75	-289	0	75	289	0	0	0	0
1267+50	1268+00	72	73		61	62	0	202	206		-141	-144	0	141	144	0	0	0	0
1268+00	1268+50	Bridge Location																	
1268+50	1269+00	Bridge Location																	
1269+00	1269+50	Bridge Location																	
1269+50	1270+00	Bridge Location																	
1270+00	1270+50	Bridge Location																	
1270+50	1271+00	Bridge Location																	
1271+00	1271+50	Bridge Location																	
1271+50	1272+00	Bridge Location																	
1272+00	1272+50	Bridge Location																	
1272+50	1273+00	Bridge Location																	
1273+00	1273+50	Bridge Location																	
1273+50	1274+00	Bridge Location																	
1274+00	1274+50	22	20		19	17	0	67	35		-48	-18	0	48	18	0	0	0	0
1274+50	1275+00	16	6		14	5	0	99	70		-85	-65	0	85	65	0	0	0	0
1275+00	1275+50	20	8		17	7	0	92	61		-75	-54	0	75	54	0	0	0	0
1275+50	1276+00	18	10		15	9	0	138	46		-123	-38	0	123	38	0	0	0	0
1276+00	1276+50	20	9		17	8	0	105	53		-88	-45	0	88	45	0	0	0	0
1276+50	1277+00	16	6		14	5	0	57	63		-43	-58	0	43	58	0	0	0	0
1277+00	1277+50	14	11		12	9	0	50	38		-38	-29	0	38	29	0	0	0	0
1277+50	1278+00	16	16		14	14	0	41	8		-27	6	0	27	0	0	0	6	0
1278+00	1278+50	17	22		14	19	0	37	4		-23	15	0	23	0	0	0	15	0
1278+50	1279+00	14	24		12	20	0	29	3		-17	17	0	17	0	0	0	17	0
1279+00	1279+50	10	22		9	19	0	11	0		-3	19	0	3	0	0	0	19	0
TOTALS		47,858	63,491	0	40,679	53,342	0	26,404	63,802	1,796	14,276	-10,460	-1,796	0	10,460	1,796	14,276	0	0



P:\Jobs\2010\20100303\3121\Site\Site.dgn\00\060133-sht-1-Schedule-Eor-tt-wrk.dgn
 9/13/2012 3:29:47 PM

USER NAME - 1654	DESIGNED - JWB	REVISED - GRAEF 09/11/2012/1
DRAWN - JWB	CHECKED - RS	REVISED -
PLLOT SCALE - 100.0000' / IN.	DATE - 06/15/2012	REVISED -
PLLOT DATE - 9/13/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31 EARTHWORK SCHEDULES	
SCALE: N.T.S.	SHEET NO. 5 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	48
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				