

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN		TRAFFIC SIGNALS 0021					LIGHTING 0021		RETAINING WALL 0040		
				ROADWAY 0003		BRIDGE 0013		IL 31 AT EB US 30 RAMPS		IL 31 AT WB US 30 RAMPS	US 30 AT RAMPS	IL 31 INTERCONNECT	KANE COUNTY	KENDALL COUNTY	KANE COUNTY
				KANE COUNTY	KENDALL COUNTY	KANE COUNTY	KANE COUNTY	VILLAGE OF MONTGOMERY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	709,910			672,860									37,050
50800515	BAR SPLICERS	EACH	2627			2627									
51200958	FURNISHING METAL SHELL PILES 14" x 0.250"	FOOT	374			374									
51202305	DRIVING PILES	FOOT	374			374									
51203200	TEST PILE METAL SHELLS	EACH	4			4									
51204650	PILE SHOES	EACH	26			26									
51500100	NAME PLATES	EACH	1			1									
52000110	PREFORMED JOINT STRIP SEAL	FOOT	385			385									
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28			28									
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	21			21									
52100510	ANCHOR BOLTS, 3/4"	EACH	104			104									
54001001	BOX CULVERT END SECTION CULVERT NO. 1	EACH	1	1											
52100520	ANCHOR BOLTS, 1"	EACH	110			110									
54011006	PRECAST CONCRETE BOX CULVERTS 10' x 6'	FOOT	36	36											
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	19	19											
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	264	264											
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	33		33										
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	28	28											
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	87	87											
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	423	423											
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	286	286											
542A1105	PIPE CULVERTS, CLASS A, TYPE 2 60"	FOOT	427	427											

\$FILES 5/23/2012 3:59:21PM

USER NAME = JGS4	DESIGNED - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	DRAWN - JWB	REVISED -
PLOT DATE = 5/23/2012	CHECKED - RS	REVISED -
	DATE - 05/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
SUMMARY OF QUANTITIES

SHEET NO. 500-5 OF 19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 V8) R-3	*	507	8
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				

Rev.