

FROM STATION	TO STATION	20200100						20400800											
		EARTH EXCAVATION			EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT ADJUSTED			EMBANKMENT			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION (SHRINKAGE FACTOR = 15%)			WASTE HAUL OFF (SWELL FACTOR 15%)		
		CU YD			CU YD			CU YD			CU YD			CU YD					
		STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage
Ramp D																			
603+50	604+00	135			115	0	0	156			-41	0	0	49	0	0	0	0	0
604+00	604+50	105			89	0	0	147			-58	0	0	68	0	0	0	0	0
604+50	605+00	179			152	0	0	100			52	0	0	0	0	0	61	0	0
605+00	605+50	227			193	0	0	100			93	0	0	0	0	0	109	0	0
605+50	606+00	174			148	0	0	251			-103	0	0	121	0	0	0	0	0
606+00	606+50	109			93	0	0	519			-426	0	0	502	0	0	0	0	0
606+50	607+00	56			48	0	0	641			-593	0	0	698	0	0	0	0	0
607+00	607+50	64			54	0	0	324			-270	0	0	317	0	0	0	0	0
607+50	608+00				0	0	0	148			-148	0	0	174	0	0	0	0	0
608+00	608+50	11			9	0	0	181			-172	0	0	202	0	0	0	0	0
608+50	609+00	85			72	0	0	180			-108	0	0	127	0	0	0	0	0
609+00	609+50	21			18	0	0	228			-210	0	0	247	0	0	0	0	0
IL 31																			
116+50	119+50		633		0	538	0		0		0	538	0	0	0	0	0	633	0
119+50	121+50		0																
121+50	123+00		78		0	66	0	139			0	-73	0	0	86	0	0	0	0
123+00	129+17		451		0	383	0	623			0	-240	0	0	282	0	0	0	0
129+17	129+50		40		0	34	0	15			0	19	0	0	0	0	0	22	0
129+50	130+00		53		0	45	0	34			0	11	0	0	0	0	0	13	0
130+00	131+50		13		0	11	0	97			0	-86	0	0	101	0	0	0	0
131+50	133+50		0		0	0	0	111			0	-111	0	0	131	0	0	0	0
133+50	134+00		0		0	0	0	10			0	-10	0	0	12	0	0	0	0
US 30																			
1238+00	1238+50	100			85	0	0	10			75	0	0	0	0	0	88	0	0
1238+50	1239+00	81			69	0	0	22			47	0	0	0	0	0	55	0	0
1239+00	1239+50	91			77	0	0	28			49	0	0	0	0	0	58	0	0
1239+50	1240+00	105			89	0	0	32			57	0	0	0	0	0	67	0	0
1240+00	1240+50	156			133	0	0	39			94	0	0	0	0	0	110	0	0
1240+50	1241+00	315			268	0	0	29			239	0	0	0	0	0	281	0	0
1241+00	1241+50	321			273	0	0	40			233	0	0	0	0	0	274	0	0
1241+50	1242+00	219			186	0	0	69			117	0	0	0	0	0	138	0	0
1242+00	1242+50	168			143	0	0	97			46	0	0	0	0	0	54	0	0
1242+50	1243+00	124			105	0	0	97			8	0	0	0	0	0	10	0	0

FILE# 5/15/2012 11:33:58 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 5/15/2012	DATE - 05/11/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31
EARTHWORK SCHEDULES**

SCALE: N.T.S. SHEET NO. 3 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	44
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				