

H:\jobs\2010\20103003\cd\sthe\cd\sthe\00\0160133-sht+Schedule-Roadway.dgn  
 6/15/2012 3:44:59 PM

LOCATION	LENGTH	AREA	60620000	60619121	60624600	21101695	60618300	63700275	X0326382	60605000	63700175	63700900	30300112	50300300
			CONCRETE MEDIAN TYPE SB-6.24	CONCRETE MEDIAN TYPE SB-6	CORRUGATED MEDIAN	TOPSOIL, FURNISH & PLACE, 30"	CONCRETE MEDIAN SURFACE, 4"	CONCRETE BARRIER DOUBLE FACE, 42"	CONCRETE BARRIER BASE (SPECIAL)	COMB CONC CURB & GUTTER, TYPE B-6.24	CONCRETE BARRIER SINGLE FACE, 42"	CONCRETE BARRIER BASE	AGGREGATE SUBGRADE IMPROVEMENT	PROTECTIVE COAT
FROM	TO	FOOT	SQ FT	SQ FT	SQ FT	SQ YD	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ YD	SQ YD
US 30														
1248+76	1248+85	9	127	127									15	15
1248+85	1260+42	1157	14,855			1,651				2,314			664	797.9
1260+42	1264+15	373	3,514			390				746			214	257.8
1264+15	1266+34	219	1,988	1,988									221	221.7
1266+34	1267+77	143						143	143				112	197.6
1274+61	1275+96	135						135	135			270	153	216.6
1275+96	1277+70	174								348	348	348	838	815.5
1277+70	1279+69	199	1,548				1,548			398	398	398	576	746.2
SUBTOTAL US 30			2,115	0	0	2,041	1,548	278	278	3,458	1,016	1,016	2,793	3,268
IL 31 (USING NBL STATIONING)														
94+73	95+26	53	877		877									
101+71	101+79	8	129	129									15	15.2
101+79	108+78	699	10,095			1,122				1,398			401	482.4
108+78	108+86	8	101	101									12	12.1
109+78	109+86	8	142	142										
109+86	114+42	456	9,269			1,030				912			262	315
114+42	115+55	113	2,957				2,957			226			65	407.3
115+55	119+97	442	8,630			959				884			254	305.3
119+97	121+06	109	1,020	1,020									114	114.2
122+84	125+43	259	1,757		1,757								196	196.1
125+43	130+74	531	6,102			678				1,062			305	366.7
130+74	133+53	279	1,827		1,827								203	203.9
134+25	134+36	11	100	100										
134+36	136+57	221	2,404			267				442			127	153.1
136+57	137+59	102	722	722									81	81.1
SUBTOTAL IL 31			2,214	3,584	877	4,056	2,957	0	0	4,924	0	0	2,035	2,652
RAMP A-B (USING RAMP A STATIONING)														
300+90	301+00	10	552					10	10				69	14.6
301+00	303+70	270						270	270				540	372.3
303+70	306+37	267						267	267				735	368.1
SUBTOTAL RAMP A-B TO STA 306+37			0	0	0	0	0	547	547	0	0	0	1344	753.3
PROJECT TOTALS			4,329	3,584	877	6,097	4,505	825	825	8,382	1,016	1,016	6,172	6,674
KENDALL COUNTY			129	0	877	873	1,108	0	0	1,181	398	398	815	981.3
KANE COUNTY			4,200	3,584	0	5,224	3,397	825	825	7,201	618	618	5,357	5,693

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 6/15/2012	DATE - 06/15/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31  
MEDIAN SCHEDULE**

SHEET NO. 1 OF 1

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	49
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				