

P:\Jobs\2010\20103003\cadd\sthe\cadd\sthe\00\0160133-sht-Schedule-SewerRemoval.dgn  
 6/15/2012 3:45:11 PM

LOCATION						50104400		HEADWALL AND FES REMOVAL (ALL ITEMS ARE PAID FOR AS STORM SEWER REMOVAL AT THE LENGTH SHOWN)						
						CONCRETE HEADWALL REMOVAL		12" HEADWALL REMOVAL (2 FT EACH)	15" HEADWALL REMOVAL (2 FT EACH)	24" HEADWALL REMOVAL (2 FT EACH)	15" FES REMOVAL (6 FT EACH)	30" FES REMOVAL (6 FT EACH)	36" FES REMOVAL (8 FT EACH)	
						10' W X 6' H (EACH)	6' W X 4' H (EACH)							
						STATION	OFFSET	LT/RT	STATION	OFFSET	LT/RT			
117+42	139	LT				1								
122+09	1.7	RT												
122+09	1.7	RT	122+09	61.6	LT									
123+39	52.5	LT					1							
126+88	43.5	RT							1					
126+88	43.5	RT	126+87	39.3	LT									
126+87	39.3	LT							1					
RAMP A														
UNKNOWN	UNKNOWN	LT	311+10	65.9	LT									
311+10	65.9	LT					1							
314+29	1.7	LT												
314+29	1.7	LT	314+30	9	RT									
314+30	9	RT					1							
RAMP B														
406+05	70.7	LT												
406+05	70.7	LT	405+89	70.7	LT									
405+89	70.7	LT												
405+89	70.7	LT	405+58	69.5	LT									
405+58	69.5	LT						1						
405+33	222.7	LT												
405+33	222.7	LT	405+23	176.5	LT									
405+23	176.5	LT						1						
RAMP C														
504+86	43.8	LT												
504+86	43.8	LT	505+04	15.8	LT									
505+04	15.8	LT					1							
RAMP D														
603+28	29.9	RT												
603+28	29.9	RT	603+28	57.1	RT									
603+28	57.1	RT						1						
605+14	54.6	LT						1						
605+14	54.6	LT	605+49	40.3	RT									
605+49	40.3	RT						1						
						KANE	3	2	10	9	5	1	0	2
						KENDALL	0	0	0	0	0	0	1	0
						TOTALS	3	2	10	9	5	1	1	2

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 6/15/2012	DATE - 06/15/2012	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31**  
**SEWER REMOVAL SCHEDULES**

SHEET NO. 6 OF 6

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	49G
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				