CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART 1	ROADWAY RECONSTRUCTION 0004				LIGHTING 0021					SIGNING 0021		UTILITIES 0043		TRAFFIC SIGNALS 0021				INTER-CONNECT 0021
				XX% FEDERAL XX% STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XX% FEDERAL XX% STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE
40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10"	SQ YD		SEE TABLE 1 ALTERNATE QUANTITIES																	
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SQ YD		SEE TABLE 1 ALTERNATE QUANTITIES																	
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	3488	3488																	
42000406	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SQ YD		SEE TABLE 1 ALTERNATE QUANTITIES																	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD		SEE TABLE 1 ALTERNATE QUANTITIES																	
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	8661	8661																	
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD		SEE TABLE 1 ALTERNATE QUANTITIES																	
42001300	PROTECTIVE COAT	SQ YD		SEE TABLE 1 ALTERNATE QUANTITIES																	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	344	92			252														
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2031	1882			109								40						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	104054	96249	375	2243	994								4193						
42400800	DETECTABLE WARNINGS	SQ FT	1193	1117			60								16						
44000100	PAVEMENT REMOVAL	SQ YD	86160	82460			3700														
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	216	216																	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	7411	7087			284								40						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	22042	20801			1241														
44000600	SIDEWALK REMOVAL	SQ FT	62600	56117			2290								4193						
44003100	MEDIAN REMOVAL	SQ FT	25667	19751			5916														
44004250	PAVED SHOULDER REMOVAL	SQ YD	2400	2400																	
44201821	CLASS D PATCHES, TYPE IV, 14"	SQ YD	1030	1030																	
48101202	AGGREGATE SHOULDERS, TYPE B	CU YD	510	510																	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	453	453																	
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	1739	1739																	
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	25	25																	
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	1834	1834																	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1																	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1																	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1																	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1																	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	4145	4145																	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	928	928																	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	272	272																	
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	225	225																	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	1152	1152																	
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	358	358																	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	3811	3811																	

△1 Rev. 9-11-12

Rev.

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - EMK	REVISED -
	DRAWN - EMK	REVISED -
PLOT SCALE =	CHECKED - SES	REVISED -
PLOT DATE =	DATE - 5/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

147TH STREET PROJECT
SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 2 OF 11 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
XX	(0405-1 & 0506-2) R-1	COOK	577	5
		CONTRACT NO. 60M57		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

P:\60254057_2941\Road\P10_147th\P10_500_SH02.dgn