CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART 1	ROADWAY RECONSTRUCTION 0004				LIGHTING 0021					SIGNING 0021		UTILITIES 0043		TRAFFIC SIGNALS 0021				INTER-CONNECT 0021
				XX% FEDERAL XX% STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XX% FEDERAL XX% STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE
60251200	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	3	2			1														
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	4	4																	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	39	30			9														
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2	2																	
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	10	2			8														
60264140	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1																	
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4																	
60500040	REMOVING MANHOLES	EACH	37	37																	
60500050	REMOVING CATCH BASINS	EACH	78	78																	
60500060	REMOVING INLETS	EACH	41	41																	
60600605	CONCRETE CURB, TYPE B	FOOT	2338	2237			101														
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2649	2649																	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	23287	22045			1242														
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	153	153																	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	177	177																	
60610900	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	78	78																	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8351	8351																	
60618800	CONCRETE MEDIAN, TYPE SB	SQ FT	7515	7515																	
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	1689	1689																	
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	3030	3030																	
X6060501	CORRUGATED MEDIAN (SPECIAL)	SQ FT	6220	3002			3218														
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1125	1125																	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2																	
1 * 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1																	
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	1	1																	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3																	
63200310	GUARDRAIL REMOVAL	FOOT	1013	1013																	
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	4218	4218																	
66400305	CHAIN LINK FENCE, 6'	FOOT	594	594																	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10600	10600																	
66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	9600	9600																	
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1																	
66900530	SOIL DISPOSAL ANALYSIS	EACH	8	8																	
66901000	BACKFILL PLUGS	CU YD	70	70																	
1 X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	28	28																	
67100100	MOBILIZATION	L SUM	1	1																	

1 Rev. 9-11-12

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - EMK	REVISED -
	DRAWN - EMK	REVISED -
PLOT SCALE =	CHECKED - SES	REVISED -
PLOT DATE =	DATE - 5/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

147TH STREET PROJECT
SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 4 OF 11 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
XX	(0405-1 & 0506-2) R-1	COOK	577	7
		CONTRACT NO. 60M57		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

P:\60254057_2941\Road\P10_147th\P10_SOQ_SHT04.dgn