

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART	ROADWAY RECONSTRUCTION 0004				LIGHTING 0021					SIGNING 0021		UTILITIES 0043		TRAFFIC SIGNALS 0021				INTER-CONNECT 0021
				XX% FEDERAL XX% STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XX% FEDERAL XX% STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE
				70103819	TRAFFIC CONTROL SURVEILLANCE	CAL DA	577	577													
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	96	96																	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6113	6113																	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	113609	113609																	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2050	2050																	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4063	4063																	
*72000100	SIGN PANEL - TYPE 1	SO FT	1431									1285	40				106				
*72000200	SIGN PANEL - TYPE 2	SO FT	49									49									
*72000300	SIGN PANEL - TYPE 3	SO FT	38									38									
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	20									18	2								
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	11									11									
72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	848									811	4				31		2		
72400320	REMOVE SIGN PANEL - TYPE 2	SO FT	277									45					224		8		
72400330	REMOVE SIGN PANEL - TYPE 3	SO FT	38									38									
*72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	SO FT	23									23									
*72400710	RELOCATE SIGN PANEL - TYPE 1	SO FT	75									42					31		2		
*72400720	RELOCATE SIGN PANEL - TYPE 2	SO FT	267									35					224		8		
*72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1787									1712	75								
*73000100	WOOD SIGN SUPPORT	FOOT	34									34									
*73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	33									33									
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SO FT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78008240	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78008270	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	FOOT	SEE TABLE 1 ALTERNATE QUANTITIES																		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1205	1173				32													
*78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	164	164																	
*78200410	GUARDRAIL MARKERS, TYPE A	SO YD	26	26																	
*78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	3	3																	

Specialty Items

Rev. 9-11-12

TYLIN INTERNATIONAL	USER NAME	DESIGNED - EMK	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	147TH STREET PROJECT SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	FLY SCALE	DRAWN - EMK	REVISOR -			XX	(0405-1 & 0506-2) R-1	COOK	577	8
	FLY DATE	CHECKED - SES	REVISOR -						CONTRACT NO.	60M57
		DATE 5/23/2012	REVISOR -							

5/23/12 10:57 AM