CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART I	ROADWAY RECONSTRUCTION 0004				LIGHTING 0021					SIGNING 0021		UTILITIES 0043		TRAFFIC SIGNALS 0021				INTER-CONNECT 0021
				XX% FEDERAL XX% STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XX% FEDERAL XX% STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE
70300520	PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	251803	251803																	
70300540	PAVEMENT MARKING TAPE, TYPE III, 6 INCH	FOOT	20141	20141																	
70300550	PAVEMENT MARKING TAPE, TYPE III, 8 INCH	FOOT	2980	2980																	
70300560	PAVEMENT MARKING TAPE, TYPE III, 12 INCH	FOOT	2566	2566																	
70300570	PAVEMENT MARKING TAPE, TYPE III, 24 INCH	FOOT	5333	5333																	
X8250060	TEMPORARY LIGHTING CONTROLLER	EACH	1					0.57	0.10			0.33									
* X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1					0.57	0.08			0.35									
* X8350012	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	10					10													
* X8360215	LIGHTPOLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	45					27				18									
* X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1														1				
* X8730255	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT	127																127		
1 * X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	619	619																	
* X8800025	SIGNAL HEAD ,LED, 1 FACE, 3 SECTION, SPAN WIRE MOUNTED	EACH	12														12				
* X8850102	INDUCTION LOOP	FOOT	100	100																	
X8900015	TEMPORARY TRAFFIC SIGNAL INTERCONNECTION SYSTEM	L SUM	1																		1
* X8950090	RELOCATE EXISTING LIGHTING CONTROLLER	EACH	2					1		1											
* X8950205	REBUILD EXISTING HANDHOLE, SPECIAL	EACH	1	1																	
~~XX000673~~	~~CUT AND CAP EXISTING WATER MAIN~~	~~EACH~~	~~22~~												~~22~~						
* 89501420	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, COMPLETE	EACH	7															2	3	2	
XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	11700												11700						
~~XX003435~~	~~PCC DRIVEWAY REMOVAL AND REPLACEMENT~~	~~SQ YD~~	~~40~~												~~40~~						
56400825	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	8												7	1					
~~XX006500~~	~~SANITARY SEWER SERVICE REMOVAL AND REPLACEMENT~~	~~FOOT~~	~~42~~												~~42~~						
X5611112	DUCTILE IRON WATER MAIN, CLASS 52, WITH POLYETHYLENE ENCASEMENT, 12"	FOOT	3251												3251						
X5611108	DUCTILE IRON WATER MAIN, CLASS 52, WITH POLYETHYLENE ENCASEMENT, 8"	FOOT	892												892						
1 * XX008154	RELOCATE EXISTING RADIO INTERCONNECT SYSTEM	EACH	2																		2
XX008156	LINE STOP 10"	EACH	1												1						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																	
Z0016702	DETOUR SIGNING	L SUM	1	1																	
Z0023204	SEDIMENT CONTROL, SILT FENCE	FOOT	15554	15171			383														
~~Z0023206~~	~~SEDIMENT CONTROL, SILT FENCE MAINTENANCE~~	~~FOOT~~	~~77770~~	~~75855~~			~~1915~~														
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2																	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3																	
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4																	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2																	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	781	781																	

1 (* Specialty Items)

1 Rev. 9-11-12

Rev.

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - EMK	REVISED -	
	DRAWN - EMK	REVISED -	
PLOT SCALE =	CHECKED - SES	REVISED -	
PLOT DATE =	DATE - 5/23/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

147TH STREET PROJECT
SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 10 OF 11 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
XX	(0405-1 & 0506-2) R-1	COOK	577	13
		CONTRACT NO. 60M57		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

p:\60254057-2941\rosd\p10_147th\P10_S00_SHT10.dgn

10:53:32 AM 7/3/2012