TABLE 1 - ALTERNATE QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL ALT A (PCC)	~~TOTAL ALT B (HMA)~~	ROADWAY RECONSTRUCTION 0004				TRAFFIC SIGNALS 0021	
					80% FEDERAL 20% STATE		100% COOK COUNTY		80% FEDERAL 20% STATE	
					ALT A	~~ALT B~~	ALT A	~~ALT B~~	ALT A	~~ALT B~~
20200100	EARTH EXCAVATION	CU YD	54505	51905	53840	51240	665	665		
31200500	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	85627	12751	85627	12751				
35501310	HOT-MIX ASPHALT BASE COURSE, 6 1/2"	SQ YD		46680		46680				
35501317	HOT-MIX ASPHALT BASE COURSE, 8 1/4"	SQ YD		22509	⚠1	22509	⚠1		⚠1	⚠1
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON		47		47				
40600300	AGGREGATE (PRIME COAT)	TON		66		66				
40600895	CONSTRUCTING TEST STRIP	EACH	⚠4	3	⚠4	3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	603	603	603	603				
40603148	POLYMERIZED HOT-MIX ASPHALT, BINDER COURSE, STONE MATRIX ASPHALT, N80	TON		7750		7750				
40603153	POLYMERIZED HOT-MIX ASPHALT, SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON		7750		7750				
⚠ 40603595	POLYMERIZED HOT-MIX ASPHALT, SURFACE COURSE, MIX 'F' N90	TON	25		25					
40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10"	SQ YD		7173		7173				
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SQ YD	7173		7173					
42000406	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SQ YD	45460		45460					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	25253	3992	21261		3992	3992		
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	2475		2475					
42001300	PROTECTIVE COAT	SQ YD	71968	39673	66721	34426	5247	5247		
(*) 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		2271		2271				
(*) 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5271	36600	5271	36600				
(*) 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	342	10989	342	10989				
(*) 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		1097		1097				
(*) 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	452	3703	452	3703				
⚠1 (*) 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		1202		1202				
(*) 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	2934	714	2876	656	58	58		
(*) 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	42168	11105	38949	7886	3219	3219		
(*) 78008230	POLYUREA PAVEMENT MARKING TYPE I- LINE 6"	FOOT	14086	8439	13752	8105	334	334		
(*) 78008240	POLYUREA PAVEMENT MARKING TYPE I- LINE 8"	FOOT	1097		1097					
(*) 78008250	POLYUREA PAVEMENT MARKING TYPE I- LINE 12"	FOOT	3387	135	3319	67	68	68		
(*) 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1533	331	1518	316	15	15		
(*) 88600100	DETECTOR LOOP, TYPE I	FOOT		3781						3781
(*) 88600700	PREFORMED DETECTOR LOOP	FOOT	4567	786					4567	786
	X4063500 PRELIMINARY TEST STRIP	EACH		2		2				

⚠ (*) Specialty Items

⚠ Rev. 9-11-12

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - EMR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN - EMR	REVISED -	
	PLOT SCALE =	CHECKED - SES	REVISED -	
	PLOT DATE =	DATE - 5/23/2012	REVISED -	

147TH STREET PROJECT
SUMMARY OF QUANTITIES (TABLE 1-ALTERNATE QUANTITIES)

SCALE: NTS | SHEET NO. 11 OF 11 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FA	(0405-1,8,0506-2) R-1	COOK	57	15
		CONTRACT NO. 60M57		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

p:\60254057-294\road\p10_147th\P10_500_SHT11.dgn

p:\60254057-294\road\p10_147th\P10_500_SHT11.dgn 5/23/2012 3:36:52 PM