

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART	ROADWAY RECONSTRUCTION				LIGHTING					SIGNING		UTILITIES		TRAFFIC SIGNALS				INTER-CONNECT
				0004				0021					0021		0043		0021				0021
				XX% FEDERAL XX% STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XX% FEDERAL XX% STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE
Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	94					70	4		3	17									
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	25					20.8	1.0			3.2									
Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	7																		7
<del>30300001</del>	<del>AGGREGATE SUBGRADE IMPROVEMENT</del>	CU YD	3410	3410																	
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1864	1864																	
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	198	198																	
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	286	286																	
Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	612	612																	
Z0062456	TEMPORARY PAVEMENT	SQ YD	22847	20914			1933														
Z0067900	STEEL CASINGS 24"	FOOT	101											101							
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	7														6.8		0.2		
<del>X0327483</del>	<del>12"x12" TAPPING SLEEVE AND VALVE IN 60" DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID</del>	EACH	1											1							
<del>X0327481</del>	<del>6"x6" TAPPING SLEEVE AND VALVE IN 60" DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID</del>	EACH	13											13							
<del>X0327482</del>	<del>8"x8" TAPPING SLEEVE AND VALVE IN 60" DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID</del>	EACH	1											1							
X5611106	DUCTILE IRON WATER MAIN, 6", CLASS 52, WITH POLYETHYLENE ENCASUREMENT	FOOT	36											36							
<del>X0327484</del>	<del>MANHOLES, TYPE A, 8'- DIAMETER, 2 - TYPE 1 FRAMES, CLOSED LIDS (SPECIAL)</del>	EACH	6	6																	
87702719	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 46 FT. AND 34 FT.	EACH	1.0															1.0			
87702795	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 65 FT. AND 40 FT.	EACH	1															1			
87702805	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 66 FT. AND 42 FT.	EACH	1															1			
81603156	UNIT DUCT, 600V, 5-1C NO. 2, 1/C NO.4 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	660							660											
<del>X0327486</del>	<del>TEMPORARY WOOD POLE, 60 FOOT, CLASS 4 (INSTALL ONLY)</del>	EACH	86					63	5		3	15									
<del>X0327485</del>	<del>MAST ARM, STREET LIGHTING 15 FT</del>	EACH	96					76	4		3	13									
82002400	TREE, MAGNOLIA ACUMINATA BUTTERFLIES (BUTTERFLIES CUCUMBER MAGNOLIA), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	1	1																	
X0327420	SANITARY SEWER, DUCTILE IRON, 8"	FOOT	42											42							
X0839900	SANITARY SEWER REMOVAL 8"	FOOT	42											42							
X5630006	CUT AND CAP EXISTING 6" WATER MAIN	EACH	12											12							
X5630008	CUT AND CAP EXISTING 8" WATER MAIN	EACH	1											1							
X5630010	CUT AND CAP EXISTING 10" WATER MAIN	EACH	1											1							

TYLIN INTERNATIONAL	USER NAME	DESIGNED - EMK	REVISED -
	PLANT SCALE	DRAWN - EMK	REVISED -
	PLOT DATE	CHECKED - SES	REVISED -
		DATE - 5/23/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**147TH STREET PROJECT  
SUMMARY OF QUANTITIES**

SCALE: NTS    SHEET NO. 10 OF 11 SHEETS    STA.    TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
XX	(0405-1 & 0506-2) R-1	COOK	577	14
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60M57	

P:\60254057-2947\Road\p10\_147\QNT\10\_500\_SHT10.dgn 5/28/2012 5:24:20 PM