

TABLE 1 - ALTERNATE QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL ALT A (PCC)	TOTAL ALT B (HMA)	ROADWAY RECONSTRUCTION				TRAFFIC SIGNALS	
					0004				0021	
					XX% FEDERAL XX% STATE		100% COOK COUNTY		XX% FEDERAL XX% STATE	
ALT A	ALT B	ALT A	ALT B	ALT A	ALT B					
20200100	EARTH EXCAVATION	CU YD	54505	51905	53840	51240	665	665		
31200502	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 4 1/2"	50 YD	85627	13751	85627	13751				
35501310	HOT-MIX ASPHALT BASE COURSE, 6 1/2"	50 YD		46686		46686				
35501317	HOT-MIX ASPHALT BASE COURSE, 8 1/4"	50 YD		22509		22509				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON		47		47				
40600300	AGGREGATE (PRIME COAT)	TON		66		66				
40600895	CONSTRUCTING TEST STRIP	EACH		3		3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	50 YD	39	603	39	603				
40603148	POLYMERIZED HOT-MIX ASPHALT, BINDER COURSE, STONE MATRIX ASPHALT, N80	TON		7750		7750				
40603153	POLYMERIZED HOT-MIX ASPHALT, SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON		7750		7750				
40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10"	50 YD		7173		7173				
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	50 YD	7173		7173					
42000406	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	50 YD	45460		45460					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	50 YD	25253	3992	21261		3992	3992		
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	50 YD	2475		2475					
42001300	PROTECTIVE COAT	50 YD	71968	39673	66721	34426	5247	5247		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT		2221		2221				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5271	36600	5271	36600				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	342	10989	342	10989				
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		1097		1097				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	452	3703	452	3703				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		1202		1202				
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	50 FT	2934	714	2876	656	58	58		
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	42168	11105	38949	7886	3219	3219		
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	14086	3439	13752	3105	334	334		
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1097		1097					
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	3387	135	3319	67	68	68		
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1533	331	1518	316	15	15		
88600100	DETECTOR LOOP, TYPE I	FOOT		3781						3781
88600700	PREFORMED DETECTOR LOOP	FOOT	4567	786					4567	786
X4063500	PRELIMINARY TEST STRIP	EACH		2		2				

TYLIN INTERNATIONAL USER NAME: _____ PLOT SCALE: _____ PLOT DATE: _____	DESIGNED: EMR DRAWN: EMR CHECKED: SES DATE: 5/23/2012	REVISED: _____ REVISED: _____ REVISED: _____ REVISED: _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	147TH STREET PROJECT SUMMARY OF QUANTITIES (TABLE 1-ALTERNATE QUANTITIES)		F.A.S. RTE.: _____ SECTION: 10405-1 & 0506-21 R 1 COUNTY: COOK TOTAL SHEETS: 577 SHEET NO.: 15	CONTRACT NO.: 60M57
	SHEET NO. 11 OF 11 SHEETS FROM: STA. _____ TO: STA. _____			FED. ROAD DIST. NO. _____ ILLINOIS FED. RD. PROJECT _____			

5/23/2012 11:23:23 AM
 5/23/2012 11:23:23 AM
 5/23/2012 11:23:23 AM