



LEGEND	
	EXISTING RIGHT-OF-WAY
	PROPOSED RIGHT-OF-WAY
	PROPOSED TEMPORARY EASEMENT

PIPE UNDERDRAINS	
STA 1072+56 LT	43 LIN FT PIPE UNDERDRAINS 4"
STA 1072+67.6 MED	11 LIN FT PIPE UNDERDRAINS 4"
STA 1072+67.6 RT	46 LIN FT PIPE UNDERDRAINS 4"
STA 1077+45.6 LT	39 LIN FT PIPE UNDERDRAINS 4"

- ① ADJ WATER MAIN 8 40 LIN FT
- 660 STA 6011+04, 40' LT MH TA 5'-DIA, TIF CL RIM = 605.25 INV = 595.45
- 661 165 LIN FT SS-JKD 36" @ 0.22%
- 662 STA 1076+50, 65' RT MH TA 8'-DIA, TIF CL RIM = 606.01 INV = 596.08 E INV = 595.08 N,W INV = 594.74 S
- 663 16 LIN FT SS-CL-A1 12" @ 1.00%
- 664 STA 1076+30, 39' RT CB TA 4'-DIA, T24 F&G RIM = 603.88 INV = 599.88
- 665 7 LIN FT SS-CL-A1 36" @ 0.57%
- 666 STA 1076+50, 78.6' RT MH TA 8'-DIA, 2-TIF CL SPL CONTROL STRUCTURE SEE DETAIL RIM = 606.12 INV = 594.70
- 667 6 LIN FT SS-CL-A1 36" @ 0.67%

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**147TH STREET PROJECT
PROPOSED DRAINAGE AND UTILITY PLAN - 147TH STREET**

SCALE: 1"=20' SHEET NO. 13 OF 23 SHEETS STA. 1071+50 TO STA. 1077+50

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(0405-1 & 0506-2) R-1	COOK	577	233
CONTRACT NO. 60M57				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				