

100% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 0044	URBAN 0044
20800150	TRENCH BACKFILL	CU YD	66	66
20101000	TEMPORARY FENCE	FOOT	43	43
21101615	TOPSOIL FURNISH AND PLACE, 4"	50 YD	204	204
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6
25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04
20101200	TREE ROOT PRUNING	EACH	3	3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4	4
28000400	PERIMETER EROSION BARRIER	FOOT	405	405
28000500	INLET AND PIPE PROTECTION	EACH	4	4
28000510	INLET FILTERS	EACH	4	4
28100107	STONE RIPRAP, CLASS A4	50 YD	15	15
28200200	FILTER FABRIC	50 YD	15	15
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	50 FT	310	310
42001300	PROTECTIVE COAT	50 YD	41	41
44000600	SIDEWALK REMOVAL	50 FT	310	310
50102400	CONCRETE REMOVAL	CU YD	1.2	1.2
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	226	226

100% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 0044	URBAN 0044
55100500	STORM SEWER REMOVAL 12"	FOOT	15	15
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1
60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	50 FT	51.4	51.4
*66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	15	15
*66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
*66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1

* Specialty Items Rev. 9-6-12

FILE NAME : c:\p\work\p\plan\handson\40273975\062611-011.psd	USER NAME : handson	DESIGNED : DRAWN : CHECKED : DATE :	REVISED : REVISED : REVISED : REVISED :	STATE OF ILLINOIS	U.S. 20 - LAKE STREET EAST OF ROSELLE ROAD / BLOOMINGDALE ROAD SUMMARY OF QUANTITIES	F.A.P. RTE. 021	SECTION 2011-069-T	COUNTY DuPAGE	TOTAL SHEETS 8	SHEET NO. 3	CONTRACT NO. 60P88
---	------------------------	--	--	-------------------	--	-----------------------	-----------------------	------------------	-------------------	----------------	--------------------