

INDEX OF SHEETS

GENERAL NOTES

IDOT STANDARDS

1. TITLE SHEET	27. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - HALSTED STREET AT 12TH STREET
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS	
3.-4. SUMMARY OF QUANTITIES	28. TRAFFIC SIGNAL PLAN - U.S. 30 (LINCOLN HWY) AT EAST END AVENUE (FOR INFORMATION ONLY)
5.-10. DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS	29. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - U.S. 30 (LINCOLN HWY) AT EAST END AVENUE
11. TRAFFIC SIGNAL PLAN - IL 1 (DIXIE HWY-CHICAGO RD) AT 16TH STREET (FOR INFORMATION ONLY)	30. TRAFFIC SIGNAL PLAN - U.S. 30 (LINCOLN HWY) AT CENTER AVENUE (FOR INFORMATION ONLY)
12. CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - IL 1 (DIXIE HWY-CHICAGO RD) AT 16TH STREET (FOR INFORMATION ONLY)	31. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - U.S. 30 (LINCOLN HWY) AT CENTER AVENUE
13. TRAFFIC SIGNAL PLAN - IL 1 (DIXIE HWY-CHICAGO RD) AT 15TH STREET (FOR INFORMATION ONLY)	32. TRAFFIC SIGNAL PLAN - U.S. 30 (LINCOLN HWY) AT WENTWORTH AVENUE (FOR INFORMATION ONLY)
14. CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - IL 1 (DIXIE HWY-CHICAGO RD) AT 15TH STREET (FOR INFORMATION ONLY)	33. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - U.S. 30 (LINCOLN HWY) AT WENTWORTH AVENUE
15.-16. TRAFFIC SIGNAL PLAN - U.S. RTE 30 (LINCOLN HWY) AT IL RTE 1 (DIXIE HWY-CHICAGO RD) (FOR INFORMATION ONLY)	34. TRAFFIC SIGNAL PLAN - U.S. 30 (LINCOLN HWY) AT STATE STREET (FOR INFORMATION ONLY)
17. SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, AND EMERGENCY VEHICLE PREEMPTION SEQUENCE - U.S. 30 (LINCOLN HWY) AT IL 1 (DIXIE HWY-CHICAGO RD)	35. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM, & EMERGENCY VEHICLE PREEMPTION SEQUENCE - U.S. 30 (LINCOLN HWY) AT STATE STREET
18. TRAFFIC SIGNAL PLAN - IL RTE 1 (CHICAGO RD) AT DIXIE HIGHWAY (FOR INFORMATION ONLY)	36.-40. INTERCONNECT PLAN
19. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - IL 1 (CHICAGO RD) AT DIXIE HIGHWAY	41. INTERCONNECT SCHEMATIC
20. TRAFFIC SIGNAL MODIFICATION PLAN - IL 1 (CHICAGO RD) AT IL 1 CUTOFF	42.-43. DISTRICT 1 STANDARD DETAILS (TC-10 AND TC-22)
21. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - IL1 (CHICAGO RD) AT IL 1 CUTOFF	
22. TRAFFIC SIGNAL PLAN - U.S. 30 (LINCOLN HWY) AT HALSTED STREET (FOR INFORMATION ONLY)	
23. SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, AND EMERGENCY VEHICLE PREEMPTION SEQUENCE - U.S. 30 (LINCOLN HWY) AT HALSTED STREET	
24. TRAFFIC SIGNAL MODIFICATION PLAN - HALSTED STREET AT 13TH STREET	
25. SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM - HALSTED STREET AT 13TH STREET	
26. TRAFFIC SIGNAL MODIFICATION PLAN - HALSTED STREET AT 12TH STREET	

THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", JANUARY 1, 2012; MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION; PROJECT SPECIFICATIONS; ALL APPLICABLE REQUIREMENTS OF THE CITY OF CHICAGO HEIGHTS; ALL APPLICABLE REQUIREMENTS OF THE ORDINANCES OF AUTHORITIES HAVING JURISDICTION; AND ALL ADDENDA THERETO SHALL GOVERN THIS WORK.

THE STANDARD SPECIFICATIONS, PROJECT SPECIFICATIONS, CONSTRUCTION PLANS, AND SUBSEQUENT DETAILS ARE ALL TO BE CONSIDERED AS PART OF THE CONTRACT. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED A PART OF THE CONTRACT.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OF UNSTABLE MATERIALS CREATED AS A RESULT THEREOF.

THE CONTRACTOR SHALL SOLELY BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.

THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.

EXISTING UTILITIES: WHEN THE PLANS OR SPECIAL PROVISIONS INCLUDE INFORMATION PERTAINING TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES, SUCH INFORMATION REPRESENTS ONLY THE OPINION OF THE ENGINEER AS TO THE LOCATION OF SUCH UTILITIES AND IS ONLY INCLUDED FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER AND OWNER ASSUME NO RESPONSIBILITY WHATSOEVER IN RESPECT TO THE SUFFICIENCY OR THE ACCURACY OF THE INFORMATION SHOWN ON THE PLANS RELATIVE TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES OR THE MANNER IN WHICH THEY ARE TO BE REMOVED OR ADJUSTED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES. THE CONTRACTOR SHALL ALSO CONTACT J.U.L.I.E. TO OBTAIN LOCATES OF THE RESPECTIVE UTILITY COMPANIES UNDERGROUND FACILITIES.

CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. AT 1-800-892-0123 AND MUST ACQUIRE A DIG NUMBER A MINIMUM OF 72 HOURS PRIOR TO ANY WORK BEING DONE

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD IN ACCORDANCE TO STANDARD SPECIFICATIONS ARTICLE 252 WHICH SHALL INCLUDE THE REQUIRED WATERING PER ARTICLE 252.08. ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 250 AND 251, RESPECTIVELY.

THE CONTRACTOR SHALL CONTACT THE IDOT TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 72 HOURS IN ADVANCE OF BEGINNING WORK.

000001-06	STANDARD SYMBOLS, ABBREVIATIONS, & PATTERNS
001006	DECIMAL OF AN INCH OF A FOOT
701001-02	OFF-RD OPERATIONS 2L, 2W, MORE THAN 15' (4.5 m) AWAY
701006-03	OFF-RD OPERATIONS 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701011-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701101-02	OFF-RD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5m) AWAY
701301-04	LANE CLOSURE 2L, 2W, SHORT TIME OPERATIONS
701501-06	URBAN LANE CLOSURE 2L, 2W, UNDIVIDED
701606-08	URBAN LANE CLOSURE MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-08	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
814001-02	HANDHOLES
857001-01	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
886001-01	DETECTOR LOOP INSTALLATIONS

FILE NAME = 4085.893-011.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, & HIGHWAY STANDARDS			F.A.P. RTE. 353	SECTION 2012-03BTS	COUNTY COOK	TOTAL SHEETS 43	SHEET NO. 2	CONTRACT # 60T86	ILLINOIS FED. AID PROJECT	
	PLOT SCALE = 1" = .0833'	DRAWN - ZCW	REVISED -		SCALE N.A.	SHEET NO. OF SHEETS	STA. TO STA.								
	PLOT DATE = 6/28/2012	CHECKED - KLB	REVISED -												
		DATE - 6/28/2012	REVISED -												

Rev. GHA #4085.893