

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY_0004		LIGHTING_0021		TRAFFIC SIGNALS_0021	
					70% STP / 30% VILLAGE OF WESTMONT	80% CMAQ / 20% STATE	70% STP / 30% VILLAGE OF WESTMONT	80% CMAQ / 20% STATE	STP / CMAQ / LOCAL FUNDING	100% VILLAGE OF WESTMONT
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	36	36					
*	20101000	TEMPORARY FENCE	FOOT	500	250	250				
	20101100	TREE ROOT PRUNING	EACH	1	1					
	20200100	EARTH EXCAVATION	CU YD	1,693	1,281	412				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	550	505	45				
	20800150	TRENCH BACKFILL	CU YD	653	418	235				
	21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,751	3,751					
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,096	936	160				
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14	12	2				
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14	12	2				
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14	12	2				
*	25200110	SOODING, SALT TOLERANT	SQ YD	1,096	936	160				
*	25200200	SUPPLEMENTAL WATERING	UNIT	11	9	2				
*	28000400	PERIMETER EROSION BARRIER	FOOT	1,370	1,030	340				
	28000510	INLET FILTERS	EACH	7	3	4				
	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	385	385					
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SC YD	4,386	3,736	650				
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SC YD	305	305					
	35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SC YD	29	29					
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	35	35					
	40600100	BITUMINGUS MATERIALS (PRIME COAT)	GALLON	759	759					
	40600300	AGGREGATE (PRIME COAT)	TON	16	16					
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	21	21					
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	35	35					
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5	3	2				
	40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	3,451	3,451					
	42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	646		646				

* DENOTES SPECIALTY ITEM
 △ DENOTES SPECIAL PROVISION

PL. 47: ALWAYS
 TO BE WORK
 NO.

PROFILE
 PLOTTED
 DATE: 06/30/12
 TIME: 10:45:00
 BY: JAB

Burns & McDonnell
 1431 OPUS PLACE, STE 400
 BOWEN'S GROVE, IL 60515
 PHONE: (630) 724-3100
 FAX: (630) 724-3201
 WEB: WWW.BURNSMCD.COM

USER NAME = #USER#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 PR. OF DES. = #DATE#

DESIGNED - JMT
 DRAWN - JAB
 CHECKED - MAP
 DATE - 01/20/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**PASQUINELLI DRIVE RECONSTRUCTION
 SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F&D RTE. 3002	SECTION 00-00083-00-FV	COUNTY	TOTAL SHEET SHEETS NO. 73 3
DUPAGE		CONTRACT NO. 63579	
ILLINOIS FED. AID PROJECT			