

SUMMARY OF QUANTITIES

SE	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY 0004		LIGHTING 0021		TRAFFIC SIGNALS 0021	
					70% STP / 30% VILLAGE OF WESTMONT	80% CMAQ / 20% STATE	70% STP / 30% VILLAGE OF WESTMONT	80% CMAQ / 20% STATE	STP / CMAQ / LOCAL FUNDING	100% VILLAGE OF WESTMONT
	42001300	PROTECTIVE COAT	SQ YD	1,557	585	952				
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	49	49					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	3,597	1,459	2,138				
	42400800	DETECTABLE WARNINGS	SQ FT	30	72	8				
	44000100	PAVEMENT REMOVAL	SQ YD	2,971	2,852	119				
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	432	432					
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,340	1,589	751				
	44000600	SIDEWALK REMOVAL	SQ FT	3,789	2,126	1,663				
	44003100	MEDIAN REMOVAL	SQ FT	870		820				
*	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	14		14				
	50901760	PIPE HANDRAIL	FOOT	89		89				
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		1				
	550A0060	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	306	186	120				
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	365	365					
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	48		48				
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	120		120				
	550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	24	24					
	56300300	ADJUSTING WATER SERVICE LINES	FOOT	40	40					
△	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2					
	60107600	PIPE UNDERDRAINS 4"	FOOT	517	430	87				
	60200905	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	3	3					
	60201205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 12 FRAME AND GRATE	EACH	7	7					
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4		4				
	60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 2 FRAME, CLOSED LID	EACH	3	2	1				
	60223800	MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2					
	60500040	REMOVING MANHOLES	EACH	1	1	0				

* DENOTES SPECIALTY ITEM
 △ DENOTES SPECIAL PROVISION

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 PROJECT: PASQUINELLI DRIVE RECONSTRUCTION
 SHEET: SUMMARY OF QUANTITIES
 DATE: 01/20/12

BURNS & MCDONNELL
 ENGINEERS ARCHITECTS
 1431 OPUS PLACE, STE 400
 DOWNERS GROVE, IL 60515
 PHONE: (630) 724-3200
 FAX: (630) 724-3201
 WEB: WWW.BURNSMCDONNELL.COM

	1431 OPUS PLACE, STE 400 DOWNERS GROVE, IL 60515 PHONE: (630) 724-3200 FAX: (630) 724-3201 WEB: WWW.BURNSMCDONNELL.COM	USER NAME = JUS279 FILE NAME = 01/15/12 PLOT SCALE = 00CALF\$ PLOT DATE = 08/27/12	DESIGNED - JMT DRAWN - JAB CHECKED - MAP DATE - 01/20/12	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PASQUINELLI DRIVE RECONSTRUCTION SUMMARY OF QUANTITIES	T.A.U. RT# 3002	SECTION 00-00083-00-PV	COUNTY	TOTAL SHEETS 73 SHEET NO. 4	CONTRACT NO. 63579
	SCALE: NONE					SHEET NO. 2 OF 6 SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT				