

SUMMARY OF QUANTITIES (CONTINUED)

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0003	BRIDGE 80% FEDERAL 20% LOCAL 0008	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021	LOCAL 0% FEDERAL 100% LOCAL
52000110	PREFORMED JOINT STRIP SEAL	FOOT	30.0		30.0				
52000216	FINGER PLATE EXPANSION JOINT, 5"	FOOT	28.0		28.0				
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	44		44				
52000365	NEOPRENE EXPANSION JOINT 6 1/2"	FOOT	44.3		44.3				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	4		4				
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	4		4				
52100520	ANCHOR BOLTS, 1"	EACH	64		64				
52100530	ANCHOR BOLTS, 1 1/4"	EACH	8		8				
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16					
54003000	CONCRETE BOX CULVERTS	CU YD	14.0	14.0					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	17	17					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	5	5					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,603	1,603	△				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	174	174					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	99	99					
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	203	203	△				
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	171	171					
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	209	209					
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,627	1,627					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	448	448					
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	844	844	△				
550B0040	STORM SEWERS, CLASS B, TYPE 1 10"	FOOT	284	284					
55100500	STORM SEWER REMOVAL 12"	FOOT	490	490					
55100700	STORM SEWER REMOVAL 15"	FOOT	728	728					
55100900	STORM SEWER REMOVAL 18"	FOOT	55	55					
55101100	STORM SEWER REMOVAL 21"	FOOT	110	110					
55101200	STORM SEWER REMOVAL 24"	FOOT	73	73					
55101400	STORM SEWER REMOVAL 30"	FOOT	105	105					
55101600	STORM SEWER REMOVAL 36"	FOOT	76	76					
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1					
58700300	CONCRETE SEALER	SQ FT	784.4		784.4				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	208		48	160			
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH	2	2					
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE II FRAME AND GRATE	EACH	12	12	△				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	10	10					
60207605	CATCH BASINS, TYPE C, TYPE B GRATE	EACH	7	7					
60207905	CATCH BASINS, TYPE C, TYPE II FRAME AND GRATE	EACH	35	35					
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	8	8					

* SPECIALTY ITEM

X CONSTRUCTION TYPE CODE 0042

△ 8/27/2012

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 9/6/2012 8:31:48 AM
 FILE NAME: 090071-sun.dgn
 PLOT DRIVER: pdf_bw_no_is_val.plt
 PLOT DATE: 9/6/2012



USER NAME = jstene	DESIGNED - JPA	REVISED -
FILE NAME = 090071-sun.dgn	DRAWN - SVJ	REVISED -
PLOT SCALE = N.T.S.	CHECKED - JLP	REVISED -
PLOT DATE = 9/6/2012	DATE - 8/24/12	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
CHARLES J. MILLER ROAD ROADWAY IMPROVEMENTS**

SCALE: N.T.S. SHEET NO. 3 OF 7 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3860	09-00372-00-PW	MCHENRY	252	6
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 63633	