SUMMARY OF QUANTITIES				0021
SP.	CODE NO.	ITEM	UNIT	TOTAL
	20101000	TEMPORARY FENCE	FOOT	305
	20200100	EARTH EXCAVATION	CU YD	541
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	700
	20400800	FURNISHED EXCAVATION	CU YD	1,434
	20800150	TRENCH BACKFILL	CU YD	18
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,080
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4,356
	25000210	SEEDING, CLASS 2A	ACRE	0.90
	25000310	SEEDING, CLASS 4	ACRE	0.10
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81
	25100630	EROSION CONTROL BLANKET	SQ YD	4,356
X	28000305	TEMPORARY DITCH CHECKS	FOOT	20
	28000400	PERIMETER EROSION BARRIER	FOOT	1,205
	28000510	INLET FILTERS	EACH	19
	28100107	STONE RIPRAP, CLASS A4	SQ YD	25
	30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	1,830
	35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	120
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,288
	40600300	AGGREGATE (PRIME COAT)	TON	13
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	280
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	110
	40600990	TEMPORARY RAMP	SQ YD	134
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	465
	40701931	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12 1/2"	SQ YD	1,080
	44000100	PAVEMENT REMOVAL	SQ YD	620
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	5,460
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,125
	44004250	PAVED SHOULDER REMOVAL	SQ YD	340
	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	275
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,250
	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	100
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	110
	50105220	PIPE CULVERT REMOVAL	FOOT	40
	542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	32
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1

* SPECIALTY ITEM
** CONSTRUCTION CODE 0042

SUMMARY OF QUANTITIES				0021
SP.	CODE NO.	ITEM	UNIT	TOTAL
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2
	54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	2
	54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1
	54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2
	54248510	CONCRETE COLLAR	CU YD	1
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	124
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	48
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	30
	55100500	STORM SEWER REMOVAL 12"	FOOT	80
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2
	60500040	REMOVING MANHOLES	EACH	1
	60500050	REMOVING CATCH BASINS	EACH	5
	60500060	REMOVING INLETS	EACH	1
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3.10
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,110
	63200310	GUARDRAIL REMOVAL	FOOT	115
	67100100	MOBILIZATION	L SUM	1
	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
	70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2.00
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,680
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ YD	182
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,026
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	638
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	60
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	135
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	90
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	560
*	X 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182
*	X 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	5,026
*	X 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	638
*	X 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	60
*	X 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	135
*	X 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	90
**	X 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
**	X 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
**	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1
**	81028190	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.	FOOT	1,100

* SPECIALTY ITEM
** CONSTRUCTION CODE 0042

GHA #4459.000

FILE NAME = 4459.000-DT1.dwg	USER NAME = BETHANY SUWINSKI	DESIGNED - JRD	REVISED -
		DRAWN - ZCW	REVISED -
	PLOT SCALE = 1" = .0833'	CHECKED - KLB	REVISED -
	PLOT DATE = 3/21/2012	DATE - 3/21/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
RANDALL ROAD AT BIG TIMBER ROAD

SCALE: N.A. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
527	08-00369-00-SP	KANE	67	3
		CONTRACT #:	63669	
		ILLINOIS FED. AID PROJECT		