

EARTHWORK												
LOCATION			UNDERCUT AND PGE REPLACEMENT	UNSUITABLE EXCAVATION (TOP SOIL)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	UTILITY EXCAVATION	EXCESS STRUCTURE EXCAVATION	TOTAL SUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
29+18	TO	36+28	15	206	221	82	-	-	82	70	36	34
36+64	TO	40+76	9	123	132	42	-	-	42	36	17	19
41+06	TO	49+55	11	151	162	65	-	-	65	56	6	50
49+73	TO	53+86	8	125	133	41	-	-	41	35	9	28
54+08	TO	58+25	9	124	133	65	-	-	65	56	24	32
TOTAL			52	729	781	295	-	-	295	253	92	161

COPIED & PLOTTED BY JAVIER & WOODMAN, INC. 7/13/2012 11:28:10 AM
 PROJECT: 110681-TCM-SCHEDULE.sht
 DRAWING: 110681-TCM-SCHEDULE.sht
 USER: jay@woodman.com
 PLOTTER: HP DesignJet T1200



DESIGNED - MWP	REVISED - IDOT/COHD REVIEW 06-25-12
DRAWN - RKM	REVISED - IDOT/COHD REVIEW 07-12-12
CHECKED - JJF	REVISED -
DATE - 06-25-12	FILE - 110681-TCM-SCHEDULE.sht

CITY OF PROSPECT HEIGHTS, ILLINOIS
SCHOENBECK ROAD
SAFE ROUTES TO SCHOOLS

SCHEDULE OF QUANTITIES

SCALE: 1" = 20'

STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2673	12-00049-00-SW	COOK	27	8
C-91-505-12		CONTRACT NO. 63731		
FED. ROAD DIST. NO.		ILLINOIS' FED. AID PROJECT M-ERTS-4009083		