

STORM STRUCTURES

STRUCTURE NUMBER	STATION	OFFSET	STRUCTURE	FRAME AND LID	RM	INVERTS		
S-16A			NOT USED					
S-16B			NOT USED					
S-17			NOT USED					
S-18			NOT USED					
S-19	50+09	42' RT	CATCH BASIN, TYPE C	TYPE 8 GRATE	666.25	663.50 (W)		
S-19A			NOT USED					
S-19B	50+97	25' R7	CATCH BASIN, TYPE C (BUILD OVER EXISTING)	TYPE 8 GRATE	668.55	FX-665.00 (S)	EX-665.00 (N)	665.00 (F)

STORM PIPES

PIPE NO.	CLASS/TYP	DIAMETER	LENGTH (FT)	SLOPE (%)	TBF (CU YD)
P-11A	NOT USED				
P-12	NOT USED				
P-13	STORM SEWER, PVC, SDR 26, 12"	12	14	0.00%	2
P-12A	NOT USED				

NOTE:
1. PRIOR TO STORM SEWER CONSTRUCTION, VERIFY LOCATION OF AT&T DUCT AND CONFIRM CATCH BASINS CAN BE INSTALLED. IF INADEQUATE DEPTH, INSTALL INLET, TYPE A (PAID FOR AS PROPOSED STORM SEWER CONSTRUCTION).

