

EARTHWORK SCHEDULE

		EARTH EXC (CUT)	EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
COUNTY	LOCATION (STA)	CU YD	CU YD	CU YD	CU YD
LEE	335+50 TO 340+00	30.8	23.1	239.6	-216.5
	495+25 TO 499+75	1	0.8	459.7	-459
	623+25 TO 628+00	30.6	23	233.4	-210.4
	714+00 TO 718+50	10.2	7.7	330.2	-322.5
	775+00 TO 777+25	0	0	13.6	-13.6
	980+75 TO 985+75	4.3	3.2	353.6	-350.4
	1085+25 TO 1090+00	6.8	5.1	234.8	-229.7
	SUB-TOTAL		83.7	62.9	1864.9
OGLE	1378+25 TO 1384+25	10.1	7.6	829.4	-821.8
	1406+00 TO 1407+75	0.6	0.5	8.9	-8.4
	1427+75 TO 1430+50	3.1	2.3	2.9	-0.6
	1461+75 TO 1466+25	67.5	50.6	183.8	-133.2
	1514+75 TO 1519+75	3.8	2.9	374	-371.1
	1567+75 TO 1572+25	44.1	33.1	149	-115.9
	1701+00 TO 1705+75	0.1	0.1	282.4	-282.3
	1780+25 TO 1786+75	1.6	1.2	974.9	-973.7
	1833+25 TO 1837+75	63.9	47.9	400.4	-352.5
	1912+50 TO 1917+50	0.9	0.7	411.5	-410.8
	1964+50 TO 1969+50	30.1	22.6	445.5	-422.9
	2042+75 TO 2047+25	29	21.8	459	-437.2
	2254+75 TO 2259+25	0.6	0.5	311.5	-311
	1410+00 TO 1412+00	1.3	1	0	1
	1479+50 TO 1481+25	0	0	0.2	-0.2
SUB-TOTAL		256.7	192.8	4833.4	-4640.6
WINNEBAGO	2360+00 TO 2365+25	0.3	0.2	597.2	-597
	2386+50 TO 2394+25	0	0	382.7	-382.7
	498+75 TO 502+25	7.6	5.7	389.4	-383.7
	507+00 TO 513+50	8	6	61.4	-55.4
	521+25 TO 524+00	5.3	4	15.2	-11.2
	SUB-TOTAL		21.2	15.9	1445.9
STEPHENSON	1161+75 TO 1169+25	18.2	13.7	11.6	2.1
SUB-TOTAL		18.2	13.7	11.6	2.1
PROJECT TOTALS		379.8	285.3	8155.8	-7870.6