	Resurfacing Table							
Location S.N. 090-0091 Pinecrest Drive	Length	Width	Area	HMA Surface Removal 1 1/4"	Temporary Ramp	Polymerized Bituminous Materials (Prime Coat)	HMA Surf Cse Mix E, N50	
	Feet	Feet	Sq Yd	Sq Yd	Sq Yd	Ton	Ton	
NBL								
59+11 TO 61+07	196	35	762.22	762	39	0.3	53.4	
SBL								
59+11 TO 61+07	196	23	500.89	501	26	0.2	35.1	
TOTAL				1263	65	0.5	88.5	

Median Removal							
Location	Sq Ft						
STA. 65+52 TO 65+86	447						
STA. 55+39 TO 55+15	234						
TOTAL	681						

Concrete Median Type SB 6.12						
Location Sq Ft						
STA. 65+80 TO 65+86 112						
STA. 55+15 TO 55+21	79					
TOTAL	191					

Urethane Pavement Marking							
	4"	4"	8"	Letters &			
Location	White	Yellow	White	Symbols			
	Foot	Foot	Foot	Sq Ft			
STA. 59+11 TO 61+07	392	392	196	20			
STA. 65+80 TO 65+86		30					
STA. 55+15 TO 55+21		18					
TOTAL	392	440	196	20			

FILE NAME =	USER NAME = toddblank	DESIGNED - D CORP	REVISED -			SCHEDULE OF QUANTITIES	F.A.P.	SECTION	COUNTY TOTAL	SHEET
\D412345-sht-pinecrest-06.dgn		DRAWN - D CORP	REVISED -	STATE OF ILLINOIS		PINECREST DRIVE INTERCHANGE	665		2433	76
	PLOT SCALE =	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION		PINECKEST DRIVE INTERCHANGE			CONTRACT NO. 68	3620
	PLOT DATE = 7/19/2012	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. A	ID PROJECT	

PCC Base Course 9"					
Location	Sq Yd				
TA. 65+80 TO 65+86	50				
TA. 55+15 TO 55+21	26				
TOTAL	76				