

LOCATION			REMOVE INLET BOX	FENCE REMOVAL	FILLING EXISTING CULVERTS	IMPACT ATTENUATOR REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL BUTT-JOINT	PAVEMENT MARKING REMOVAL	DELINEATOR REMOVAL
ROAD	STATION FROM	STATION TO	EACH	FOOT	EACH	EACH	SQ YD	SQ FT	EACH
I-474	-	456+00.00	0	0	0	0	0	2012	0
I-74	456+00.00	471+00.00	1	0	0	2	190	2008	0
I-74	471+00.00	486+00.00	0	1463	0	0	308	1452	0
I-74	486+00.00	501+00.00	1	756	0	2	0	871	0
I-74	501+00.00	516+00.00	0	2520	0	0	0	1113	0
I-74	516+00.00	531+00.00	0	2014	0	0	0	2521	15
RAMP G/H	118+50.00	101+47.00	0	1672	0	0	0	0	34
I-74	531+00.00	546+00.00	0	617	0	0	0	2116	0
I-74	546+00.00	561+00.00	0	1613	0	0	0	1835	0
I-74	561+00.00	576+00.00	0	3081	0	0	0	1701	2
I-74	576+00.00	591+00.00	0	2284	0	0	0	3417	39
I-74	591+00.00	606+00.00	0	0	0	2	0	2962	28
I-74	606+00.00	621+00.00	0	0	0	0	553	1914	13
I-74	621+00.00	636+00.00	0	0	0	0	0	383	0
I-74	636+00.00	640+00.00	0	0	0	0	0	54	0
I-155	00+00.00	09+00.00	2	2307	0	0	0	2874	0
I-155	09+00.00	23+00.00	1	473	0	0	544	1349	0
I-155	23+00.00	37+50.00	0	0	0	0	0	2616	0
I-155	37+50.00	51+00.00	0	0	0	0	0	882	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	881	0
Morton Ave.	28+25.00	36+50.00	0	0	1	0	0	2452	17
Morton Ave.	36+50.00	44+75.00	0	45	0	0	0	1684	11
Morton Ave.	44+75.00	58+00.00	0	372	0	0	0	1428	0
TOTAL			5	19,217	1	6	1,595	38,525	159

**NOTE**

- SEE SIGN SCHEDULE SHEETS FOR EACH STAGE FOR REMOVAL SCHEDULES ASSOCIATED WITH SIGNS AND SIGN STRUCTURES.
- SEE SCHEDULE OF QUANTITIES FOR EACH STAGE FOR PAVEMENT MARKING REMOVAL SCHEDULE.

FILE NAME =	DESIGNED - HTL	REVISED -		<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REMOVAL SCHEDULE OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D468620-shd-schedule-rm-2.dgn	DRAWN - KV	REVISED -						*	90-[14R(14HB-4,14,14HVB)BR]	TAZEWELL	2433	78
USER NAME = TERRA	CHECKED - DA/LVA	REVISED -			SCALE:      SHEET NO. 2 OF 85 SHEETS      STA.      TO STA.			CONTRACT NO. 68620				
PLOT DATE = 7/29/2012	DATE - 7/20/2012	REVISED -			ILLINOIS FED. AID PROJECT							