LOCATION			AGGREGATE SUBGRADE IMPROVEMENT 8"	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	PIPE UNDERDRAINS 4"	TEMPORARY PAVEMENT REMOVAL	AGGREGATE SHOULDER REMOVAL	WHITEWASHING FOR CONCRETE PAVEMENT	TEMPORARY PAVEMENT
ROAD	STATION FROM	STATION TO	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	SQ YD
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	0	332	332	104	316	285	0	0	332	717
I-74	471+00.00	486+00.00	0	0	0	141	0	0	0	0	0	1413
I-74	486+00.00	501+00.00	0	0	0	0	0	0	0	0	0	0
I-74	501+00.00	516+00.00	0	0	0	0	0	0	0	0	0	0
I-74	516+00.00	531+00.00	0	0	0	204	0	0	0	0	0	4322
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0	0
I-74	531+00.00	546+00.00	0	0	0	171	0	0	0	0	0	1692
I-74	546+00.00	561+00.00	0	0	0	15	0	0	0	0	0	326
I-74	561+00.00	576+00.00	0	0	0	0	0	0	0	0	0	0
I-74	576+00.00	591+00.00	0	221	221	87	210	192	0	0	221	3041
I-74	591+00.00	606+00.00	0	84	84	52	79	89	0	0	84	263
I-74	606+00.00	621+00.00	0	155	155	167	147	133	0	0	155	2300
I-74	621+00.00	636+00.00	0	292	292	28	278	250	0	0	292	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0
I-155	00+00.00	09+00.00	0	0	0	73	0	0	0	0	0	1587
I-155	09+00.00	23+00.00	0	0	0	0	0	0	0	0	0	0
I-155	23+00.00	37+50.00	0	299	299	1	299	0	0	0	299	0
I-155	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0	34
Morton Ave.	36+50.00	44+75.00	0	330	330	80	293	0	0	0	330	353
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0
		TOTALS	0	1713	1713	1123	1622	949	0	0	1713	16048

	GLARE SCREEN (NEW LOCATION)	GLARE SCREEN TO REMAIN	GLARE SCREEN ON-SITE	TEMPORARY CONCRETE BARRIER (NEW LOCATION)	TEMPORARY CONCRETE BARRIER TO REMAIN	TEMPORARY CONCRETE BARRIER ON-SITE
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
TOTALS	0	0	0	0.0	0.0	0.0

LOCATION			PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	PAVEMENT MARKING TAPE, TYPE III 24"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 12"
ROAD	STATION FROM	STATION TO	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0
I-74	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0
I-74	486+00.00	501+00.00	0	0	0	0	0	0	0	0	0
I-74	501+00.00	516+00.00	0	0	0	0	0	0	0	0	0
I-74	516+00.00	531+00.00	0	0	0	0	0	0	0	0	0
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0
I-74	531+00.00	546+00.00	0	939	0	0	0	0	0	0	0
I-74	546+00.00	561+00.00	0	600	0	0	0	0	0	0	0
I-74	561+00.00	576+00.00	0	2000	0	0	0	0	0	0	0
I-74	576+00.00	591+00.00	0	1562	0	0	0	0	0	0	0
I-74	591+00.00	606+00.00	0	2464	0	0	0	0	0	0	0
I-74	606+00.00	621+00.00	0	2300	0	0	0	0	0	0	0
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0
I-155	00+00.00	09+00.00	0	0	0	0	0	0	0	0	0
I-155	09+00.00	23+00.00	0	0	0	0	0	0	0	0	0
I-155	23+00.00	37+50.00	0	76	0	0	0	0	0	0	0
I-155	37+50.00	51+00.00	0	1224	0	0	0	0	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	0	158	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	15	1144	0	0	0	0	0	0	0
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	0	0	0	0
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0
		TOTALS	15	12467	0	0	0	0	0	0	0

	SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
	FOOT	CAL MO
TOTAL PRE STAGE A	623	3.25

ATTENUATOR LOCATION SCHEDULE				IMPACT ATTENUATORS WIDE NEW OR RELOCATED	IMPACT ATTENUATORS WIDE TO REMAIN	IMPACT ATTENUATORS NARROW NEW OR RELOCATED	IMPACT ATTENUATORS NARROW TO REMAIN
ROAD	STATION	OFFSET	TYPE	EACH	EACH	EACH	EACH
			(NO ATTENUATORS THIS STAGE)				

	TEST LEVEL 2 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 2 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDRCTVE), TEST LVL 2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDRCTVE, NARROW TEST LVL 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDRCTVE, TEST LVL 2	IMPACT ATTENUATORS, RELOCATE (NON-REDRCTVE), TEST LVL 2
WIDE	0	0	0	0	-	-	0
NARROW	0	0	0	-	0	0	-

	TEST LEVEL 3 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 3 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDRCTVE), TEST LVL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDRCTVE, NARROW TEST LVL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDRCTVE, TEST LVL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDRCTVE), TEST LVL 3
WIDE	0	0	0	0	-	-	0
NARROW	0	0	0	-	0	0	-

FILE NAME = D468620-sht-schedule-00.dgn	DESIGNED - HTL	REVISED -	TERRA ENGINEERING LTD.
USER NAME = TERRA	DRAWN - KV	REVISED -	**STATE OF ILLINOIS**
PLOT DATE = 7/29/2012	CHECKED - DA/LVA	REVISED -	**DEPARTMENT OF TRANSPORTATION**
	DATE - 7/20/2012	REVISED -	

MAINTENANCE OF TRAFFIC
PRE STAGE SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. 3 OF 85 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	90-[14R;(14HB-4,14,14HVB)BR]	TAZEWELL	2433	79
		CONTRACT NO. 68620		
	ILLINOIS FED. AID PROJECT			