

LOCATION			AGGREGATE SUBGRADE IMPROVEMENT 8"	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	PIPE UNDERDRAINS 4"	TEMPORARY PAVEMENT REMOVAL	AGGREGATE SHOULDER REMOVAL	WHITEWASHING FOR CONCRETE PAVEMENT	TEMPORARY PAVEMENT	GLARE SCREEN (NEW LOCATION)	GLARE SCREEN TO REMAIN	GLARE SCREEN ON-SITE	TEMPORARY CONCRETE BARRIER (NEW LOCATION)	TEMPORARY CONCRETE BARRIER TO REMAIN	TEMPORARY CONCRETE BARRIER ON-SITE	
ROAD	STATION FROM	STATION TO	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0	0	0	0	9528	0.00	0.00	17950.00	
I-74	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	637.50		
I-74	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	200.00		
I-74	486+00.00	501+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	1100.00	TEMPORARY CONCRETE BARRIER FROM PREVIOUS STAGE	
I-74	501+00.00	516+00.00	0	0	0	0	0	0	0	0	0	0	0	110		0.00	2312.50		
I-74	516+00.00	531+00.00	0	0	0	0	0	0	0	0	0	0	0	1501		0.00	2787.50		
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0	0	333	1206		337.50	2787.50		
I-74	531+00.00	546+00.00	0	0	0	0	0	0	1011	53	0	0	1572	0		1787.50	0.00		
I-74	546+00.00	561+00.00	0	0	0	0	0	0	678	8	0	0	1503	0		1737.50	0.00		
I-74	561+00.00	576+00.00	0	0	0	0	0	0	0	0	0	0	332	1168	FOOT	337.50	1162.50	FOOT	
I-74	576+00.00	591+00.00	0	0	0	0	0	0	0	0	0	0	0	1500	9534	0.00	2225.00	19812.00	
I-74	591+00.00	606+00.00	0	0	0	0	0	0	0	0	0	0	0	304		0.00	1162.50		
I-74	606+00.00	621+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00	RELOCATE TEMPORARY CONCRETE BARRIER	
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00		
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00		
I-155	00+00.00	09+00.00	0	0	0	0	0	0	1032	44	0	0	0	0		0.00	762.50		
I-155	09+00.00	23+00.00	0	0	0	0	0	0	1502	48	0	0	0	0		0.00	1337.50		
I-155	23+00.00	37+50.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	62.50	FOOT	
I-155	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00	4200.00	
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00		
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00	TEMPORARY CONCRETE BARRIER	
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00		
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00		
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0	0	0		0.00	0.00		
TOTALS			0	0	0	0	0	0	4223	153	0	0	TOTALS	3740	5788	FOOT 0	4200.00	13750.00	FOOT 0.00

LOCATION			PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	PAVEMENT MARKING TAPE, TYPE III 24"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 12"
ROAD	STATION FROM	STATION TO	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0
I-74	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0
I-74	486+00.00	501+00.00	0	0	0	0	0	0	0	0	0
I-74	501+00.00	516+00.00	0	0	0	0	0	0	0	0	0
I-74	516+00.00	531+00.00	0	0	0	0	0	472	1497	0	0
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0
I-74	531+00.00	546+00.00	0	0	0	0	0	2539	7259	217	0
I-74	546+00.00	561+00.00	0	4686	0	0	0	2925	2851	47	0
I-74	561+00.00	576+00.00	0	4157	0	0	0	1601	0	0	0
I-74	576+00.00	591+00.00	0	671	0	0	0	224	0	0	0
I-74	591+00.00	606+00.00	0	0	0	0	0	0	0	0	0
I-74	606+00.00	621+00.00	0	0	0	0	0	0	0	0	0
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0
I-155	00+00.00	09+00.00	0	0	0	0	0	0	0	0	0
I-155	09+00.00	23+00.00	0	0	0	0	0	0	0	0	0
I-155	23+00.00	37+50.00	0	0	0	0	0	0	0	0	0
I-155	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	0	0	0	0
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0
TOTALS			0	9515	0	0	0	7762	11607	264	0

	SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
	FOOT	CAL MO
TOTAL STAGE 7B	1,069	6.75

ATTENUATOR LOCATION SCHEDULE				IMPACT ATTENUATORS WIDE NEW OR RELOCATED EACH	IMPACT ATTENUATORS WIDE TO REMAIN EACH	IMPACT ATTENUATORS NARROW NEW OR RELOCATED EACH	IMPACT ATTENUATORS NARROW TO REMAIN EACH
ROAD	STATION	OFFSET	TYPE				
I-74	525+95.21	120.59	WIDE		1	0	0
I-74	525+14.62	29.51	WIDE		1	0	0
I-74	603+86.03	-5.37	WIDE		1	0	0
I-74	464+05.09	1.01	WIDE		1	0	0
I-74	576+72.17	43.99	NARROW		0	0	1
I-74	544+29.04	202.18	WIDE	1	0	0	0
I-155	34+90.76	-57.71	WIDE		1	0	0
I-155	18+05.41	-38.97	NARROW		0	0	1
MORTON	32+13.36	42.84	WIDE		1	0	0

	TEST LEVEL 2 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 2 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDUCTIVE), TEST LVL 2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDUCTIVE, NARROW, TEST LVL 2)	IMPACT ATTENUATORS, RELOCATE (FULLY REDUCTIVE, TEST LVL 2)	IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LVL 2
WIDE	0	1	1	0	-	-	0
NARROW	0	0	0	-	0	0	-

	TEST LEVEL 3 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 3 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDUCTIVE), TEST LVL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDUCTIVE, NARROW, TEST LVL 3)	IMPACT ATTENUATORS, RELOCATE (FULLY REDUCTIVE, TEST LVL 3)	IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LVL 3
WIDE	1	5	6	0	-	-	1
NARROW	0	2	2	-	0	0	-