

LOCATION			AGGREGATE SUBGRADE IMPROVEMENT 8"	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	PIPE UNDERDRAINS 4"	TEMPORARY PAVEMENT REMOVAL	AGGREGATE SHOULDER REMOVAL	WHITEWASHING FOR CONCRETE PAVEMENT	TEMPORARY PAVEMENT
ROAD	STATION FROM	STATION TO	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	SQ YD
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	33	0	0	0	0
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	146	0	0	0	0
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0
TOTALS			0	0	0	0	0	179	0	0	0	0
LOCATION			PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	PAVEMENT MARKING TAPE, TYPE III 24"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 12"	
ROAD	STATION FROM	STATION TO	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	
Morton Ave.	16+00.00	28+25.00	35	1515	0	0	0	564	0	0	0	
Morton Ave.	28+25.00	36+50.00	18	3025	0	0	24	1339	0	0	0	
Morton Ave.	36+50.00	44+75.00	26	3016	0	0	40	1111	0	0	0	
Morton Ave.	44+75.00	58+00.00	18	1047	0	0	13	427	0	0	0	
TOTALS			97	8603	0	0	77	3441	0	0	0	

TOTAL STAGE 14C	SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
	FOOT	CAL MO
	434	0.75

NOTE

MORTON STAGE 14 SUB C INDEPENDENT FROM I-74/I-155 STAGE 14

STAGE 14 SUB STAGE C

LOCATION			WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	TEMPORARY PAVEMENT REMOVAL
ROAD	STATION TO	STATION FROM	SQ FT	FOOT	FOOT	SQ YD
I-474	456+00.00	-	46	0	41	0
I-74	471+00.00	456+00.00	1789	0	752	0
I-74	486+00.00	471+00.00	2658	0	100	0
I-74	501+00.00	486+00.00	2812	0	0	0
I-74	516+00.00	501+00.00	3973	0	0	0
I-74	531+00.00	516+00.00	4079	0	0	0
RAMP G/H	101+47.00	118+50.00	0	0	0	0
I-74	546+00.00	531+00.00	3159	0	0	0
I-74	561+00.00	546+00.00	3119	0	0	0
I-74	576+00.00	561+00.00	2484	0	0	0
I-74	591+00.00	576+00.00	4154	0	0	0
I-74	606+00.00	591+00.00	2349	0	0	811
I-74	621+00.00	606+00.00	1530	456	1322	65
I-74	636+00.00	621+00.00	22	0	17	0
I-74	640+00.00	636+00.00	0	0	0	0
I-155	09+00.00	00+00.00	0	0	0	0
I-155	23+00.00	09+00.00	0	0	0	0
I-155	37+50.00	23+00.00	0	0	0	0
I-155	51+00.00	37+50.00	0	0	0	0
I-155	66+00.00	51+00.00	0	0	0	0
Morton Ave.	28+25.00	16+00.00	264	0	0	0
Morton Ave.	36+50.00	28+25.00	1788	0	0	0
Morton Ave.	44+75.00	36+50.00	2070	0	0	0
Morton Ave.	58+00.00	44+75.00	1020	0	0	0
TOTALS			37,317	456	2,232	876

TOTAL POST CONST	SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
	FOOT	CAL MO
	134	0

POST CONSTRUCTION

FILE NAME = D468620-sh1-schedule-14C.dgn	DESIGNED - HTL	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC - SCHEDULE OF QUANTITIES STAGE 14 - SUB STAGE C / POST CONSTRUCTION	F.A.I. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = TERRA	DRAWN - KV	REVISED -				90-[14R(14HB-4,14,14HB)BR]	TAZEWELL	2433	155	
PLOT DATE = 7/29/2012	CHECKED - DA/LVA	REVISED -				CONTRACT NO. 68620				
	DATE - 7/20/2012	REVISED -	SCALE: SHEET NO. 79 OF 85 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				