


SCHEDULE OF SHARED PAY ITEMS

CODE NUMBER	DESCRIPTION	UNIT	TOTAL	ROADWAY* FAI 74 / FAI 155	I-155 OVER I-74 (RAMPS G & H)	I-74 OVER ABANDONED RAILROAD DEMOLITION	I-74 OVER JEFFERSON ST	I-74 OVER US 150 (JACKSON ST)	I-74 / I-155 OVERHEAD SIGN STRUCTURES	MORTON AVE. OVER I-74	TRAFFIC SIGNALS	LIGHTING	SIGNING	LANDSC APING	ITS	PINECREST DR	EVP
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	267,195	267,195	-	-	-	-	-	-	-	-	-	-	-	-	-
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	267,195	267,195	-	-	-	-	-	-	-	-	-	-	-	-	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,222	1,595	800	1,027	-	800	-	-	-	-	-	-	-	-	-
40600990	TEMPORARY RAMP	SQ YD	6,505	6,000	134	172	-	134	-	-	-	-	-	-	-	65	-
40603360	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	708.20	-	166.20	211.20	-	242.30	-	-	-	-	-	-	-	88.50	-
44003100	MEDIAN REMOVAL	SQ FT	34,533	33,852	-	-	-	-	-	-	-	-	-	-	-	681	-
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	18,515	18,515	-	-	-	-	-	-	-	-	-	-	-	-	-
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	68,449	68,449	-	-	-	-	-	-	-	-	-	-	-	-	-
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,040,980	1,180	264,120	-	297,740	461,500	-	16,440	-	-	-	-	-	-	-
60107600	PIPE UNDERDRAINS 4"	FOOT	53,339	53,339	-	-	-	-	-	-	-	-	-	-	-	-	-
64301090	ATTENUATOR BASE	SQ YD	236	134	-	-	-	-	-	-	-	-	-	-	102	-	-
78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,002	982	-	-	-	-	-	-	-	-	-	-	-	20	-
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	144,345	143,513	-	-	-	-	-	-	-	-	-	-	-	832	-
78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	22,174	21,978.00	-	-	-	-	-	-	-	-	-	-	-	196.00	-
80400100	ELECTRIC SERVICE INSTALLATION	EACH	4	-	-	-	-	-	-	-	-	3.00	-	-	1.00	-	-
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	22,358	-	-	-	-	-	-	-	3,129	2,141	-	-	17,088	-	-
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	430	-	-	-	-	-	-	-	200	-	-	-	230	-	-
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	15,989	-	-	-	-	-	-	-	-	14,869	-	-	1,120	-	-
81400200	HEAVY-DUTY HANDHOLE	EACH	24	4	-	-	-	-	-	-	-	-	-	-	20	-	-
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	15	-	-	-	-	-	-	-	13	-	-	-	2	-	-
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	30,930	-	-	-	-	-	-	-	1,831	19,446	-	-	9,653	-	-
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	99	-	-	-	-	-	-	-	39	-	-	-	60	-	-
87900200	DRILL EXISTING HANDHOLE	EACH	6	-	-	-	-	-	-	-	1	-	-	-	5	-	-
88600100	DETECTOR LOOP, TYPE I	FOOT	2,644	1,200	-	-	-	-	-	-	1,444	-	-	-	-	-	-
X0324159	WHITEWASHING FOR CONCRETE PAVEMENT	SQ YD	267,195	267,195	-	-	-	-	-	-	-	-	-	-	-	-	-

* ROADWAY IS FURTHER BROKEN DOWN AS SHOWN BELOW

CODE NUMBER	DESCRIPTION	UNIT	Roadway on Roadway Column	Drainage on Roadway Column	Structural on Roadway Column	Electrical on Roadway Column	IDOT ITS on Roadway Column	IDOT Traffic on Roadway Column	MOT on Roadway Column (TERRA)	Pavement Marking on Roadway Column (KEG)	TOTAL OF ROADWAY COLUMN FAI 74 / FAI 155
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	258,244	-	-	-	-	-	8,951	-	267,195
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	258,244	-	-	-	-	-	8,951	-	267,195
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	-	-	-	-	-	-	1,595	-	1,595
40600990	TEMPORARY RAMP	SQ YD	-	-	-	-	-	-	6,000	-	6,000
40603360	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	-	-	-	-	-	-	-	-	-
44003100	MEDIAN REMOVAL	SQ FT	-	-	-	-	-	-	33,852	-	33,852
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	12,142	-	-	-	-	-	6,373	-	18,515
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	59,924	-	-	-	-	-	8,525	-	68,449
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	-	140	1,040	-	-	-	-	-	1,180
60107600	PIPE UNDERDRAINS 4"	FOOT	-	45,472	-	-	-	-	7,867	-	53,339
64301090	ATTENUATOR BASE	SQ YD	-	134	-	-	-	-	-	-	134
78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	-	-	-	-	-	-	-	982	982
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	-	-	-	-	-	-	-	143,513	143,513
78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	-	-	-	-	-	-	-	21,978.00	21,978
80400100	ELECTRIC SERVICE INSTALLATION	EACH	-	-	-	-	-	-	-	-	-
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	-	-	-	-	-	-	-	-	-
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	-	-	-	-	-	-	-	-	-
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	-	-	-	-	-	-	-	-	-
81400200	HEAVY-DUTY HANDHOLE	EACH	-	-	-	-	4	-	-	-	4
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	-	-	-	-	-	-	-	-	-
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	-	-	-	-	-	-	-	-	-
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	-	-	-	-	-	-	-	-	-
87900200	DRILL EXISTING HANDHOLE	EACH	-	-	-	-	-	-	-	-	-
88600100	DETECTOR LOOP, TYPE I	FOOT	-	-	-	-	1,200	-	-	-	1,200
X0324159	WHITEWASHING FOR CONCRETE PAVEMENT	SQ YD	258,244	-	-	-	-	-	8,951	-	267,195

FILE NAME : ...D:\68620\sh\schedule_08.dgn	DESIGNED : -	REVISED : -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF SHARED PAY ITEMS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME : jneambillo	DRAWN : -	REVISED : -				* 90-114R(14HB-4,14,14HB)BR	TAZEWELL	2433	700	
PLOT DATE : 7/27/2012	CHECKED : -	REVISED : -				CONTRACT NO. 68620	ILLINOIS FED. AID PROJECT			